



CITY OF TAMPA

Pam Iorio, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 2

DATE: July 13, 2010

Contract: 10 - C-00038; Swann Avenue Pipe Rehabilitation

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

- Item 1: Traffic Concerns: Swann Avenue is a 2-lane collector road with a center left turn lane. In June 2008, it was at LOS of B with a peak PM volume of 395 vehicles per hour. A Right-of-Way Use Permit is required for the project, the cost of which shall be included in the Base Bid, including all Management of Traffic requirements necessary to perform the work. No additional payment for R/W permits and MOT requirements will be authorized.
- Item 2: The number of joints included in the Base Bid: Based on a total length of 1,680 feet and assuming the individual pipe lengths are 8 feet, approximately 210 joints comprise the total project.

The Contractor shall include 210 repair joints in the Lump Sum Bid. Fifteen percent (15%) of these joint repairs shall be made using the extra wide size bands, and the remaining 85% shall be made using the regular size bands (32 seals will be extra wide, 178 seals will be regular size). The intent of the project is to band every joint in the entire pipe run indicated. Based on this intent, the actual number of joints repaired will be adjusted to the actual number found in the field. Appropriate adjustments will be made using the unit costs provided on the revised page P-3R. Additionally, per the contract specification, the installer is to follow the manufacturer's recommendations regarding the size of band needed for the joint. If the quantity of joint bands required for the work differs from that specified, then an appropriate adjustment in the contract value will be made using the prices indicated in the Schedule of Unit Prices.

- Item 3: Replace Proposal page P-3 with the attached page P-3R.
- Item 4: A video of the pipe included in the Scope of Work is posted on the City's website at

http://www.tampagov.net/dept_contract_administration/programs_and_services/construction_project_bidding/index.asp

The video is three years old, and is the only visual reference available.

- Item 5: An owner's contingency of \$30,000 shall be included in the Lump Sum Bid to accommodate the authorization of additional work (i.e. regular size bands and extra wide bands). All additional work will be authorized at the discretion of the Engineer. See page P-3R for clarification.
- Item 6: Cleaning of the line: The entire length of pipe run indicated in the Scope of Work shall be thoroughly cleaned, with a jet truck, prior to starting the work. Refer to the specifications for disposal requirements of solids and other debris as a result of the cleaning process.

This addendum shall be included in and attached to the inside cover of the Contract Documents by and upon which bids are submitted.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect.

Questions are to be e-mailed to Contract Administration@tampagov.net.



Jim Greiner, P.E., Contract Manager

Proposal

The Contractor shall furnish all labor, materials, and equipment, construct, test and maintain and complete the Swann Avenue Pipe Rehabilitation as shown on the plans and specifications, specified, and directed by the Engineer.

The proposed work comprises installation of approximately 210 pipe joint seals in the existing 43" x 68" elliptical reinforced concrete pipe (178 seals regular size, 32 seals extra wide) in Swann Avenue between the retention pond at S. Packwood Avenue and S. Howard Avenue, including pipe preparation, stormwater flow diversion, Bahia/St. Augustine sod replacement, mobilization, MOT, testing, videotaping, and all appurtenant work to complete the project. Include a \$30,000 owner's contingency in lump sum price, for use as directed by owner.

The total Lump Sum Price, including owner's \$30,000 contingency allowance, for Contract 10-C-00038, Swann Avenue Pipe Rehabilitation is:

_____ dollars
and _____ cents(\$_____).

OWNERS CONTINGENCY ALLOWANCE

Use the contingency allowance only as directed by the Engineer.

The Contractor's related costs for services, products and equipment ordered by the Engineer under the contingency allowance are not part of the Contract Sum. These costs include delivery, installation, taxes, insurance, equipment rental, and similar costs.

Work Directive Change Orders authorizing use of funds from the contingency allowance will include Contractor's related costs and reasonable overhead and profit margins.

At Project closeout, credit unused amounts remaining in the contingency allowance to the Owner by Change Order.

SCHEDULE OF UNIT PRICES

Unit prices are the total installed price for each item. Installed prices shall include all General Conditions, materials, labor and supervision, MOT, required for a complete installation. Unit prices shall be honored by the Contractor through substantial completion of Work.

<u>Item</u>	<u>Description</u>	
1	Furnish and Install 56.25" regular EPDM WEKO-Seal as specified	\$ _____/each (in figures)

_____ Dollars
(in words)

2	Furnish and install 56.25" extra wide EPDM WEKO-Seal as specified	\$ _____/each (in figures)
---	---	-------------------------------

_____ Dollars
(in words)