



CITY OF TAMPA

Pam Iorio, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 3

DATE: NOVEMBER 18, 2008

08-C-00027; Bern's Park Fountain Improvements –(SLBE Sheltered Market)

Bidders on the above referenced project are hereby notified that the following clarifications are made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

- Item 1: Project Scope Clarification: The scope of work is as indicated on Sheet One of 3 Sheets dated 09/04/08. Disregard the cover sheet that shows palm trees, signage and decorative fencing, as part of the scope.
- Item 2: Fountain Drainage Clarification: Fountain is to be filled with hose from existing water connection on site. Fountain is to be drained or pumped out when needed. No sanitary connection is required.
- Item 3: Electrical Requirements Clarification: Electrical design documents are a basis of bid. Contractor shall submit electrical drawings, prepared by Engineer licensed in the State of Florida. Design shall encompass all related electrical work including electrical panel requirements for a complete project. Applicable permits shall be obtained by the Contractor for this work.
- Item 4: Fountain Equipment Clarification: Fountain equipment design intent is as a basis of performance criteria. The Contractor shall submit full design drawings for plumbing and pump equipment as shop drawings for approval. Applicable permits shall be obtained by the Contractor for this work. Fountain drawings shall be prepared by an Engineer licensed in the State of Florida.
- Item 5: Fountain Finish Clarification: Finish for the fountain is per sheet Three of 3 dated 09/04/08. The specifications of the tile is the basis of design.
- Item 6: Sheet 3 of 3; Component Details, dated 11/06/07; the AWO-050 water sensor shall be deleted.
- Item 7: Sheet S-2.0, Sections and Details, Steel Type in Fountain Slab Clarification: The steel mat that is closer to the soil in the bottom pool area shall be Grade 60 steel. The upper mat closer to the water is to be corrosion resistant steel.
- Item 8: Sodding Clarification: Sod only areas damaged as a result of the work.
- Item 9: Sheet 2 of 3; Piping & Lighting, dated 11/06/07; Equipment List Clarification: Up lights and stub ups quantity of 12 shall be revised to 17.

All other provisions of the Contract Documents and Specifications not in conflict with this clarification shall remain in full force and effect.

Jim Greiner, P.E., Contract Manager
Contract Administration Department

306 E. Jackson Street, 4N • Tampa, Florida 33602 • (813) 274-8456 • FAX: (813) 274-8080

www.tampagov.net