



CITY OF TAMPA

Pam Iorio, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 2

DATE: January 13, 2011

09-C-00032; ARRA-SCG Fire Station 22 Improvements – Rebid

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

- Item 1: Sheet LA-100 and LA-101 plant material Clarification: Follow plant schedule quantities for plant/tree/shrub and ground cover counts. Follow plans to implement design concept.
- Item 2: Section 07411 Manufactured Roof Panels; Part 2 Products; Roof Panel Assemblies, Page 4; Revise width of panel to **16"**.
- Item 3: Sheet S-1.1, revise wind speed to 130 mph
- Item 4: Sheet LA-101, Boulder Clarification: Provide Random Boulders varying in size from 2'x2'x2' to the large ones as 4'x4'x4'. similar to florida native limestone, similar to stone found at www.wingatesupplyinc.com
- Item 5: Sheet C-6, Main drive clarification: Drive to be Concrete to match apron per FDOT Index No. 305.
- Item 6: Sheet C-8, Jack and bore for water line installation across existing drive is required.
- Item 7: Existing 6" well to be grouted and capped.
- Item 8: Roof overhang clarification; Overhang is 2'-0".
- Item 9: Apparatus Bay Ceiling Clarification: Delete ceiling requirement in Section 09512, Page 7. Ceiling will be suspended gypsum board. exterior grade.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to Contract Administration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Manager