



# CITY OF TAMPA

Pam Iorio, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

## ADDENDUM NO. 1

**DATE: February 4, 2011**

Contract 10-C-00040; El Centro Espanol Roof Replacement Rebid

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: Delete second detail cut symbol designated by 5/A.03.02 at junction of east wall of Roof Drainage Level 1 and sloped 'S' style clay roof located north of Roof Drainage Level 2. The Scope of Work at that junction and the similar junction south of Roof Drainage Level 2 is as follows:

1. Existing 'S' style clay roof along rake wall: Remove a minimum of 36" of clay tiles and store and protect for reinstallation, spud back roof membrane as required for removal of existing galvanized steel rake flashing and counter flashing.
2. Reinstall existing 'S' style clay tiles after installation of new copper rake flashing and counter flashing. Install a new 18" wide and continuous strip of ice and water shield underlayment over new roof edge before reinstallation of clay roof tiles.

Item 2: Roof Scope Revisions; delete roof work at roof dormer on roof facing east (Howard Avenue) side. Delete roof edge flashing similar to (2/A,03.03), to approximately 4'-0" linear feet to either side North and South of dormer. This work is as shown but not limited to sheets - A.01.01 and A.03.01.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to [ContractAdministration@tampagov.net](mailto:ContractAdministration@tampagov.net).

*Jim Greiner*

Jim Greiner, P.E., Contract Manager