



CITY OF TAMPA

Pam Iorio, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 3

DATE: July 15, 2010

Contract 10-C-00040; El Centro Espanol Roof Replacement

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: Delete second detail cut symbol designated by 5/A.03.02 at junction of east wall of Roof Drainage Level 1 and sloped 'S' style clay roof located north of Roof Drainage Level 2. The Scope of Work at that junction and the similar junction south of Roof Drainage Level 2 is as follows:

1. Existing 'S' style clay roof along rake wall: Remove a minimum of 36" of clay tiles and store and protect for reinstallation, spud back roof membrane as required for removal of existing galvanized steel rake flashing and counter flashing.
2. Reinstall existing 'S' style clay tiles after installation of new copper rake flashing and counter flashing. Install a new 18" wide and continuous strip of ice and water shield underlayment over new roof edge before reinstallation of clay roof tiles.

This Addendum shall be included in and attached to the inside cover of the Contract Documents by and upon which bids are submitted.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to ContractAdministration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Manager