11-C-00003; Howard F. Curren AWTP Piping and Conduit Rehabilitation

Item No.	Description	Unit	Approx. Quantity	Wharton-Smith, Inc. Unit Price	Wharton-Smith, Inc. Total	Kimmins Contracting Corp Unit Price	Kimmins Contracting Corp Total	Westra Construction Corp Unit Price	Westra Construction Corp Total	Garney Companies, Inc Unit Price	Garney Companies, Inc Total	Prime Construction Group, Inc Unit Price	Prime Construction Group, Inc Total
100	Contingency	LS	1	$ 50,000.00	$50,000.00	$ 50,000.00	$50,000.00	$ 50,000.00	$50,000.00	$ 50,000.00	$50,000.00	$ 50,000.00	$50,000.00
200	Furnish and install 950 LF of 63" (IPS-OD) DR-26 HDPE liner pipe, (1) 63" (IPS-OD) DR-26 fabricated HDPE 90o bend (FL/FL), cement grout to fill annular space around liner pipe, insertion pits and access openings required to install HDPE pipe, including construction, trenching, backfilling, and restorations, as specified, temporary relocation of the 6" cooling water discharge pipe within Screen and Grit Building #1 and relocation of the 14" DIP thickening tanks overflow pipe, and fabricate (5) stop logs, including stop log installation and removal and cleaning of effluent conduit and effluent pipes	LS	1	$ 980,450.00	$980,450.00	$913,552.36	$913,552.36	$1,040,000.00	$1,040,000.00	$1,302,000.00	$1,302,000.00	$1,356,000.00	$1,356,000.00
650	Debris removal and disposal	CY	530	$ 65.00	$34,450.00	$13.81	$7,319.30	$150.00	$79,500.00	$45.00	$23,850.00	$200.00	$106,000.00
4800.1	Concrete restoration up to 1" thick	SF	300	$ 15.00	$4,500.00	$39.32	$11,796.00	$17.00	$5,100.00	$17.00	$5,100.00	$18.00	$5,400.00
4800.2	Concrete restoration 1" to 3" thick	SF	350	$ 38.00	$13,300.00	$50.62	$17,717.00	$42.50	$14,875.00	$40.00	$14,000.00	$44.00	$15,400.00
4800.3	Concrete restoration 3" to 5" thick	SF	2400	$ 49.00	$117,600.00	$73.13	$175,512.00	$55.00	$132,000.00	$51.00	$122,400.00	$56.00	$134,400.00
4800.4	Concrete restoration with CPP epoxy paste (250 mils thickness)	SF	600	$ 42.00	$25,200.00	$56.25	$33,750.00	$47.00	$28,200.00	$46.00	$27,600.00	$48.00	$28,800.00
4800.5	Concrete restoration with epoxy (125 mils thickness)	SF	3000	$ 13.50	$40,500.00	$28.13	$84,390.00	$15.00	$45,000.00	$16.00	$48,000.00	$16.00	$48,000.00
				TOTAL	$1,266,000.00	**TOTAL**	$1,294,036.66	**TOTAL**	$1,394,675.00	**TOTAL**	$1,592,950.00	**TOTAL**	$1,744,000.00

Notice of Intent to Award: Unless subsequently indicated otherwise, in a revised posting, the City of Tampa intends to award the referenced project to the lowest bidder listed in this tabulation. A bidder aggrieved by this decision may file a protest not later than 4:30 P.M., three (3) business days from the first posting hereof, pursuant to City of Tampa Code Chapter 2, Article V, Division 3, Section 2-282, Procurement Protest Procedures. Protests not conforming therewith shall not be reviewed.

Bids Received By: Jim Greiner

Jim Greiner, PE
Contract Manager
Contract Administration Dept.
306 E. Jackson Street, 4N
Tampa, FL 33602