

Item No.	Description	Unit	Approx. Quantity	Unit Price in Words	Unit Price	Total Computed Price	
Schedule A - Riverwalk Segment 11, Phase 6B							
SP-14.02	CLEARING AND GRUBBING	LS	1		\$	\$	
SP-17.01.1	GRANITE PAVERS - ARCHITECTURAL (F&I) - PLANKS	SF	3,200		\$	\$	
SP-17.02	RAILING SYSTEM NO. 2 - OVER WATER	LF	240		\$	\$	
ELECTRICAL							
SP-25.01-01	LIGHTING CONTRACTOR W/ENCLOSURE, PANELBOARD, ETC.	LS	1		\$	\$	
SP-25.01-02	SERVICE METER, DISCONNECT AND FEEDER	LS	1		\$	\$	
SP-25.01-03	J/B IP67 RATED, 18"X6"	EA	1		\$	\$	
SP-25.01-04	J/B NEMA 4X, 8"X8"X6" W/SUBMERSIBLE SPLICE KITS	EA	40		\$	\$	
SP-25.01-05	1-1/2" PVC SCHEDULE 40 UNDERGROUND CONDUIT	EA	200		\$	\$	
SP-25.01-06	1" LFNC, MEETING IP67	LF	500		\$	\$	
SP-25.01-07	1/2" LFNC, MEETING IP67	LF	200		\$	\$	
SP-25.01-08	1/2" PVC SCHEDULE 80 EMBEDDED IN WALKWAY AND TO STEP LIGHT	LF	200		\$	\$	
SP-25.01-09	#8 AWG WIRE (XHHW-2)	LF	2,700		\$	\$	
SP-25.01-10	#12 AWG WIRE (XHHW-2)	LF	2,500		\$	\$	
SP-25.01-11	STEP LIGHT FLUORESCENT 13 WATTS	EA	39		\$	\$	
SITE FURNITURE							
721-74-1	LANDSCAPEFORMS PARCVUE RECEPTACLE	EA	1		\$	\$	
721-180	OLDE TOWNE FIBERGLASS PLANTER	LS	4		\$	\$	
SP-11.16	CONTINGENCY	LS	1	FIFTY THOUSAND DOLLARS AND NO CENTS	\$ 50,000.00	\$ 50,000.00	
					Schedule A SubTotal	\$	\$

Item No.	Description	Unit	Approx. Quantity	Unit Price in Words	Unit Price	Total Computed Price
	Schedule B - Riverwalk - Whiting Street Seawall Repair					
0101-1	Mobilization	LS	1		\$	\$
125-4-2	Excavation of Fill and Debris	CY	6		\$	\$
400-4-5	Cast-in-Place Concrete Slab on Grade	CY	4.6		\$	\$
400-4-8	Cast-in-Place Concrete Sheet Pile Cap	CY	6.7		\$	\$
415-1-6	Reinforcing Steel - Slab on Grade	LB	602		\$	\$
415-1-8	Reinforcing Steel - Sheet Pile Cap	LB	890		\$	\$
0120-72	#57 Stone Fill	CY	24		\$	\$
0514-71-1	Geotextile	SY	116.7		\$	\$
SP-08.10	Floating Turbidity Barrier	LF	85		\$	\$
SP-14.03	Concrete Demolition	CY	10		\$	\$
SP-15.05.1	Concrete Rehabilitation - Crack Injection	LF	5		\$	\$
SP-15.05.2	Concrete Rehabilitation - Epoxy	GAL	2		\$	\$
SP-15.05.3	Concrete Rehabilitation - Spall Repair	CF	9.8		\$	\$
SP-15.05.4	Concret Rehabilitation - Removal and Patching of Miscellaneous Steel	CF	1		\$	\$
SP-17.03	Walkway Railing System without Lighting (Furnish & Install)	LF	70		\$	\$
SP-11.16	Contingency	LS	1	Five Thosand Dollars and No Cents	\$ 5,000	\$ 5,000
				Schedule B - SubTotal	\$	\$
				Total A & B	\$	\$