



CITY OF TAMPA

Bob Buckhorn, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 3

DATE: September 19, 2011

Contract 11-C-00054; North Tampa Closed Basins, Phase 1

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

RFI and Responses

1. What are the sod limits?
Response: Any area disturbed by construction activities outside the pond must be covered with sod.
2. Does the bottom of the reservoir get seed & mulch, or is sod required?
Response: All slopes of the pond shall be sodded for approximately 20 feet toward the toe of slope and then either sod, or seed and mulch, can be installed for the remaining slope and bottom.
3. Is onsite burning permissible?
Response: No.
4. The permanent base and pavement required to complete the storm work is included in Bid Items 0285-701 and 0337-7-2, is that correct?
Response: Yes.
5. The storm line Bid items would only include any temporary base or pavement that might be required to complete the work, is that correct?
Yes.
6. Wooden bollards should be included with the fence bid item, is that correct?
Response: Yes.
7. Bid Item 0337-7-2, the permanent pavement surface replacement is by the SY, is the bid item to meant to include (detail on C-11):
Response:
 - a. the 1" mill and pave outside the trench areas Yes
 - b. the 1.5" type S-1 structural course in the trench areas Yes

306 E. Jackson Street, 4N • Tampa, Florida 33602 • (813) 274-8456 • FAX: (813) 274-8080

- c. and the 1" type S-3 wearing course in the trench areas? Yes
8. The Pump Station Asphalt drive (bid item 0350-2-2) is to include all sub base work, base materials, base installation and the required asphalt is this correct? I.e. it's a stand alone item.
Response: Yes.
9. Are precast structures (storm MH, pump station, etc.) acceptable?
Response: Yes.
10. There is no standard detail for the storm manholes included in the drawings
Response: The Stormwater Division has no standard detail for manholes. Please use FDOT Index 200 and, as specified in Section 425 Stormwater Inlets, Manholes, and Junction Boxes, ASTM C478.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to ContractAdministration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor