



CITY OF TAMPA

Bob Buckhorn, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 1

DATE: August 18, 2011

Project: 11-C-00056; Tampa Convention Center Loading Dock Expansion Joint Replacement

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

- Item 1: Proposal, page P-4; REPLACE** existing P-4 page with attached page P-4R.
- Item 2: Specification Section 01017: Alternates, 3.2 Alternate No. 2 (Additive); DELETE** 750 l.f. of expansion joint material and replace with 60 l.f. of expansion joint material.
- Item 3: On Site Parking clarification:** Parking on the loading dock area will be limited to company vehicles only, and must not interfere with daily loading dock operations. All personal and other vehicles can park in any public parking areas available including the Convention Center garage.
- Item 4: Sheet R-502; Repair Detail 35.3, ADD** the following note: Field verify existing gutter so new gutter can match the existing gutter being replaced. Gutter shall be formed aluminum (white), 0.040 inch gauge, K gutter profile with concealed splice joints. Provide gutter brackets (maximum 2'-0" o.c. spacing) and flat ends with finish that matches gutters.
- Item 5: Sheet R-502; Repair Detail 35.3, DELETE** the note: "See Photo 6 on Sheet R-502 for additional details" and replace with the following note: "See Photo 6 on Sheet R-511 for additional details."

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect.

For questions concerning the above referenced project, please fax to 813/274-8080.



Jim Greiner, P.E., Contract Manager

Contract 11-C-00056; Tampa Convention Center Loading Dock Expansion Joint Replacement

Contract Item No.	Estimated Quantity	Description and Price in Words	Computed Total Price for Item in Figures
ALTERNATE NO. 2	LS	This includes the furnishing of all labor, equipment, and material for the replacement of approximately 60 l.f. of expansion joint material in the exhibition hall along with a protective steel cover plate with all associated work required for a complete project in accordance with the Contract Documents.	
(ADDITIVE)		<p>_____</p> <p>_____ dollars</p> <p>and _____ cents</p>	
	LS	(ADDITIVE)	\$ _____