



CITY OF TAMPA

Mayor Pam Iorio

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

LETTER OF CLARIFICATION 2

DATE: December 4, 2008

Contract: 7-C-60; Seminole Gardens Center Improvements

Bidders on the above referenced project are hereby notified that the following clarification is made to the Contract Documents:

- Item 1: Drawing L-1, **ADD:** general note to state 'existing wood rail & 6"x 6" post fence to be removed.
- Item 2: Drawing A-5.3 – **Clarify:** Disregard keynote #4 on sheet A-5.3
- Item 3: Drawing E-0.1 – **Clarify:** See attached sketch of revised electrical riser diagram
- Item 4: Drawing E-0.1 – **Clarify:** Panel "B" shall be a 225-amp M. L. O. panel.
- Item 5: Drawing C-2.0 - **Clarify:** Hand hole location is to be at base of existing light pole north of A/C enclosure as indicated on Sheet C-2.0.
- Item 6: Drawing E-3.1 – **Clarify:** Electrical contractor is to furnish and install (2) Duray TSW121RW light fixtures in each of (4) cabinets and connect to circuit wiring indicated on plans..
- Item 7: Drawing M-0.1 – **ADD:** Note required hood fire suppression system on kitchen hood schedule sheet M-0.1 and see fan schedule for hood exhaust fan equipment.
- Item 8: Drawing E-0.1 – **ADD:** Contractor is required to remove and properly dispose of all existing electrical conduit, wiring, devices, boxes, fixtures, equipment and distribution equipment. All work to be new. All conduit shall be concealed.

Jim Greiner, P.E., Contract Manager
Contract Administration Department

DRAWING TITLE:
REVISED ELECTRICAL RISER DIAGRAM

DATE:
 12/04/08

JOB NO.
 207027

REF. SHEET
 E-0.1


DRAWING NO.
 ESK-1

LYLE

ENGINEERING
GROUP, INC.

SCOTT LOUIS LYLE, PE
 FL. LIC. PE 32734

CONSULTING ENGINEERS
 8308 N. SAUL RAY ST.
 TAMPA, FLA. 33604



813 935 5009

EB005380

PROJECT NAME:

**SEMINOLE GARDEN
 CENTER RENOVATION**
 5810 CENTRAL AVENUE
 TAMPA, FLORIDA 33604

