

Skate Park at New Tampa Community Park Supplemental Information to RFQ

March 2007

Please find the attached preliminary site plan as a visual aid in identifying the proposed site improvements. It is very important to note that the Recreation Center Building, the Vehicular Entrance/Exit, Parking Lot, and Sidewalks adjacent to the proposed Skatepark are not part of the project.

The proposed improvements to the site include a skatepark consisting of modular and concrete elements. Approximately half of the +/-18,750 square foot skatepark will consist of modular elements on a flat slab. Those elements include a mini-pipe, fun box combo, spine, grindrails, tables, etc. The other part of the park will be constructed out of concrete as depicted in the concept plan. Other park amenities may be included such as fencing, bleachers, small playground, mister, outdoor fans, lighting, etc. An existing drainpipe located in the approximate center of the skatepark will need to be extended to the appropriate location to capture stormwater from the skatepark.

This scope is subject to change and supplementation during the design phase. It is anticipated that coordination with various City departments and interested community groups will be required.

It is recognized that the attached drawing represents the conceptual plan. Design modification, coordination with the General Contractor currently constructing the Recreation Center building, project construction, and other strategies to complete the skatepark improvements will be evaluated throughout the duration of the project. The selected firm will be an active participant in that process and is expected to provide expertise in developing the project budget and making recommendations regarding the final scope of work.