



CITY OF TAMPA

Pam Iorio, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 1

DATE: SEPTEMBER 11, 2008

Project: 6-C-49; Rebid: Interbay Pool Restroom Renovations and Pool Deck Repair; PW6682

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

- Item 1: Alternate No. 1, Foundation Stabilization Plan Sheet 2 Clarification:
Project note that refers to pumping soil/cement/water mixture into void under slab, bidder should estimate that the grout intake for each location should be 50 cubic yards. The estimated depth of injection is approximately 15 feet below the surface. Verification of cubic yards utilized shall be with Truck Tickets or other recognized industry standards.
- Item 2: Architectural Sheet A-2 Paver Clarification Key note #3:
new 6"x9" thick concrete pavers on pool deck shall be Dura-Thin 6"x9" rectangles by C & D Thin Pavers. They are 1 1/4" thick nominal.
- Item 3: Architectural Sheet A-2 Sidewalk Clarification Keynote 14:
For portion of new ramp on sidewalk in existing right-of-way, it should comply with State of Florida DOT Index #304.
- Item 4: Plumbing Sheet P-4 Sanitary Isometric Clarification:
Note on Sanitary Isometric which reads, "Cap for future water fountain" should instead read "Raise existing water fountain to proper ADA height after finishing pool deck."

This addendum shall be included in and attached to the inside cover of the Contract Documents by and upon which bids are submitted.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect.

For questions concerning the above referenced project, please fax to 813/274-8080.

Jim Greiner, P.E., Contract Manager
Contract Administration Department

306 E. Jackson Street, 4N • Tampa, Florida 33602 • (813) 274-8456 • FAX: (813) 274-8080

TampaGov
www.tampagov.net