



CITY OF TAMPA

Pam Iorio, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 2

DATE: July 14, 2008

Project: Fletcher Ave. Force Main Replacement: Rome Ave. to N. Boulevard

Project No.: Contract 08-C-00020

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: Replace page P-4 with attached page P-4R.

Item 2: On sheet 1 of the plan set, add the following note: "ATTENTION IS DIRECTED TO THE FACT THAT THESE PLANS MAY HAVE BEEN REDUCED IN SIZE BY REPRODUCTION. THIS MUST BE CONSIDERED WHEN OBTAINING SCALED DATA."


Item 3: On sheet 20 of the plan set, in the Pavement Restoration Detail, change the MILL AND OVERLAY 1" OF TYPE FC-5 ASPHALT FRICTION BASE note to read: "MILL AND OVERLAY 3/4" OF TYPE FC-5 ASPHALT FRICTION COURSE "

Item 4: On sheet 20 of the plan set, in the Pavement Restoration Note number 7, change the reference from 1-inch to "3/4-inch".

This addendum shall be included in and attached to the inside cover of the Contract Documents by and upon which bids are submitted.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect.

For questions concerning the above referenced project, please fax to 813/274-8080.



Jim Grejner, P.E., Contract Manager
Contract Administration Department

306 E. Jackson Street, 4N • Tampa, Florida 33602 • (813) 274-8456 • FAX: (813) 274-8080


www.tampagov.net

Item No.	Description	Unit	Approx Quantity	Unit Price in Words	Unit Price	Total Computed Price
4900	Connect to Existing Manhole, includes inside Drop	Ea	1	\$	\$	\$
5003.60	Manhole Rehabilitation, Coating of 60-inch Dia. Bottom Chamber	S.F.	85	\$	\$	\$
5051	Filling of Existing Sanitary Sewers	C.Y.	52	\$	\$	\$
7000.4	4" Dia. Plug Valve with Box	Ea	6	\$	\$	\$
7500	Air Release Valve Assembly	Ea	4	\$	\$	\$
8000.9	Superpave Asphalt Base Course, Type B-12.5, 9-inches thick	S.Y.	94	\$	\$	\$
8100.75	Asphalt Concrete Friction Course, FC-5, 3/4-inch thick	S.Y.	1238	\$	\$	\$
8100.2	Superpave Asphalt Concrete, Course Type SP-12.5, 2-inches thick	S.Y.	141	\$	\$	\$
8604	Permanent 4" Thick Concrete Sidewalk	S.Y.	6	\$	\$	\$
8900.3	St-Augustine Sod	S.Y.	100	\$	\$	\$
9100.10	10" Dia. Line Stop	Ea	1	\$	\$	\$
9600	Videotaping	L.S.	1	\$	\$	\$
10000.4	Connections between 4" PVC & HDPE	Ea	4	\$	\$	\$
10000.10	Connections between 10" PVC & HDPE	Ea	4	\$	\$	\$
TOTAL \$						