



CITY OF TAMPA

Pam Iorio, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 1

DATE: January 15, 2008

Contract 08-C-00025; Waverly Place Stormwater Pipe Relocation

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

PLAN SHEETS

- Item 1: Sheet 3, Structure S-3, invert for 15" RCP to be read as 9.25.
- Item 2: Sheet 3, Structure S-4, invert for 15" RCP to be read as 10.00.
- Item 3: Sheet 3, Structure S-5, add invert for exist 15" RCP = 10.08.
- Item 4: Sheet 5, Off-set proposed 6"WM @ sta. 2+62 under existing 15" RCP.
- Item 5: Sheet 6, Delete notes #6 and #7.
- Item 6: Sheet 7, Typical section of Euclid Ave. to include "Milling and resurfacing the north side of roadway." Also add note "Payment for milling to be included in the various paving items and no additional payment shall be made for this work."

PROPOSAL

- Item 7: Replace pages P-3 and P-4 with the attached pages P-3R and P-4R.

SPECIFICATIONS

- Item 8: Add on page SP-20, SP- 132 Milling
Milling for existing asphalt will be included in the various contract items for pavement replacement and no additional payment shall be made therefor.
- Item 9: Add, on page SP-20, SP -133 Existing trees
The Contractor shall protect existing grand tree roots at 3604 and 3605 Waverly Place. All root pruning shall be performed by a certified arborist.

This addendum shall be included in and attached to the inside cover of the Contract Documents by and upon which bids are submitted.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect.

Questions may be directed to Jim Greiner, P.E.: Telephone (813) 274-8598, fax (813) 274-8080, or e-mail Jim.Greiner@tampagov.net.



Jim Greiner, P.E., Contract Manager
Contract Administration Department

306 E. Jackson Street, 4N • Tampa, Florida 33602 • (813) 274-8456 • FAX: (813) 274-8080

TampaGov
www.tampagov.net

Item No.	Description	Unit	Approx. Quantity	Unit Price in Words	Unit Price	Total Computed Price
101	Mobilization	L.S.	1	\$	\$	\$
102-1	Maintenance of Traffic	L.S.	1	\$	\$	\$
160-5-2	Type "C" Stabilization 12"	S.Y.	630	\$	\$	\$
190	Tree Removal (>12" to 18" Dia.)	EA.	1	\$	\$	\$
285-705	ABC-III 4 0" Thick	S.Y.	675	\$	\$	\$
331-72-10	Type S Asphalt 1 0" (S-3)	S.Y.	1,000	\$	\$	\$
350-1-1	Concrete Driveway 6"	S.Y.	110	\$	\$	\$
425-1-910	Inlet (City Standard - Type 1)	EA.	1	\$	\$	\$
425-2-71	Manhole (J-7)	EA.	4	\$	\$	\$
425-2-72	Manhole (J-7) w/Type 1 Inlet Top	EA.	1	\$	\$	\$
430-1-126	Concrete Pipe Culvert 36"	L.F.	369	\$	\$	\$
430-11-423	Concrete Pipe Culvert 15" Dia. Class IV	L.F.	50	\$	\$	\$
520-1-10	Standard Curb & Gutter Type "F"	L.F.	800	\$	\$	\$
1706	6" Dia. PVC House Lateral (SDR-35 or AWWA C900)	L.F.	70	\$	\$	\$
1706	8" Dia. PVC House Lateral (SDR-35 or AWWA C900)	L.F.	66	\$	\$	\$
3506	6" Flexible Adapter	EA.	4	\$	\$	\$
5000	Filling Ex. Stormwater	C.Y.	60	\$	\$	\$
8900	Sodding (St. Augustine Bahia)	S.Y.	450	\$	\$	\$
8500	Sodding (St. Augustine)	S.Y.	450	\$	\$	\$

Item No.	Description	Unit	Approx. Quantity	Unit Price in Words	Unit Price	Total Computed Price
9200	Root Pruning	L.F.	100	\$ _____	\$ _____	\$ _____
9600	Project Videotaping	L.S.	1	\$ _____	\$ _____	\$ _____
"W-1003-6	6" Water Main Offset/Relocation Complete	EA	2	\$ _____	\$ _____	\$ _____
W-2300-6	Furnish and Install 6" Water Main	L.F.	200	\$ _____	\$ _____	\$ _____
W-3322	Furnish and Install 6" Bend	EA	10	\$ _____	\$ _____	\$ _____
W-5305	3/4" Water Main Short Service Connection	EA	5	\$ _____	\$ _____	\$ _____
W-5305-1	3/4" Water Main Long Services Connection	EA	2	\$ _____	\$ _____	\$ _____
"W5335	Transfer/Relocate Existing Water Meter	EA	2	\$ _____	\$ _____	\$ _____
TOTALS \$				\$ _____	\$ _____	\$ _____