



CITY OF TAMPA

Pam Iorio, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 2

DATE: SEPTEMBER 26, 2007

Contract 7-C-43; Sewer Rehabilitation by Cured-In-Place Pipe, (C.I.P.P.) FY-07


Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: Replace Proposal pages P-3R, P-4R and P-5R with attached P-3RR, P4RR and P5RR.

This addendum shall be included in and attached to the inside cover of the Contract Documents by and upon which bids are submitted.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect.

Questions may be directed to Jim Greiner, P.E.; Telephone (813) 274-8598, fax (813) 274-8080, or e-mail Jim.Greiner@tampagov.net.



Jim Greiner, P.E., Contract Manager
Contract Administration Department

Item No.	Description	Unit	Approx. Quantity	Unit Price in Words	Unit Price	Total Computed Price
100	Contingency	LS	1	Thirty-Five Thousand Dollars and No Cents	\$ 35,000.00	\$ 35,000.00
101	Mobilization for MH Rehab. (if less than 3 manholes)	EA	3			
102-60	Work Zone Signs	E.D.	500			
102-74-1	Barricades Type I or II	E.D.	5,000			
102-76	Arrow Board	E.D.	100			
0408.2360	Cured in Place Pipe for 8" Dia. Gravity Sewer (0.236 inch thick)	LF	1,000			
0410.2950	Cured in Place Pipe for 10" Dia. Gravity Sewer (0.295 inch thick)	LF	1,000			
0412.2950	Cured in Place Pipe for 12" Dia. Gravity Sewer (0.295 inch thick)	LF	1,000			
0415.2950	Cured in Place Pipe for 15" Dia. Gravity Sewer (0.295 inch thick)	LF	1,000			
0418.3540	Cured in Place Pipe for 18" Dia. Gravity Sewer (0.354 inch thick)	LF	1,000			
0421.4130	Cured in Place Pipe for 21" Dia. Gravity Sewer (0.413 inch thick)	LF	500			
0424.4720	Cured in Place Pipe for 24" Dia. Gravity Sewer (0.472 inch thick)	LF	500			
0427.4720	Cured in Place Pipe for 27" Dia. Gravity Sewer (0.472 inch thick)	LF	500			
0430.5310	Cured in Place Pipe for 30" Dia. Gravity Sewer (0.531 inch thick)	LF	500			
0436.7090	Cured in Place Pipe for 36" Dia. Gravity Sewer (0.709 inch thick)	LF	500			
0601	Hydraulic Cleaning & Inspection of Gravity Sewer	LF	7,000			
0602	Mechanical Cleaning of Gravity Sewer	LF	1,000			
0621	Cleaning & Inspection of Tuberculated Cast Iron or Ductile Iron Sewer, less than 15" Dia.	LF	1,000			

Item No.	Description	Unit	Approx. Quantity	Unit Price in Words	Unit Price	Total Computed Price
0622	Cleaning & Inspection of Tuberculated Cast Iron or Ductile Iron Sewer, 15" Dia. & Greater	LF	1,500			
0650	Additional Cleaning & Inspection of Gravity Sewer	LF	500			
0700	Disposal of Debris	CY	200			
2050	Reconnect Service Connections	EA	300			
2051	Removal of Protruding Services	EA	20			
2052	Root Removal	LF	100			
4800	Manhole Rehabilitation by Coating System	SF	1,000			
9050.08	Sewage Bypass Pumping for 8" Dia. Sewer	LF	1,000			
9050.10	Sewage Bypass Pumping for 10" Dia. Sewer	LF	1,000			
9050.12	Sewage Bypass Pumping for 12" Dia. Sewer	LF	1,000			
9050.15	Sewage Bypass Pumping for 15" Dia. Sewer	LF	1,000			
9050.18	Sewage Bypass Pumping for 18" Dia. Sewer	LF	1,000			
9050.21	Sewage Bypass Pumping for 21" Dia. Sewer	LF	500			
9050.24	Sewage Bypass Pumping for 24" Dia. Sewer	LF	500			
9050.27	Sewage Bypass Pumping for 27" Dia. Sewer	LF	500			
9050.30	Sewage Bypass Pumping for 30" Dia. Sewer	LF	500			
9050.36	Sewage Bypass Pumping for 36" Dia. Sewer	LF	500			
SUB TOTAL SCHEDULE A						

Item No.	Description	Unit	Approx. Quantity	Unit Price in Words	Unit Price	Total Computed Price
Schedule B						
0408.2361	Increase/Reduction of 0.059" Thickness for 8" Dia. Gravity Sewer	LF	1,000			
0410.2951	Increase/Reduction of 0.059" Thickness for 10" Dia. Gravity Sewer	LF	1,000			
0412.2951	Increase/Reduction of 0.059" Thickness for 12" Dia. Gravity Sewer	LF	1,000			
0415.2951	Increase/Reduction of 0.059" Thickness for 15" Dia. Gravity Sewer	LF	1,000			
0418.3541	Increase/Reduction of 0.059" Thickness for 18" Dia. Gravity Sewer	LF	1,000			
0421.4131	Increase/Reduction of 0.059" Thickness for 21" Dia. Gravity Sewer	LF	500			
0424.4721	Increase/Reduction of 0.059" Thickness for 24" Dia. Gravity Sewer	LF	500			
0427.4721	Increase/Reduction of 0.059" Thickness for 27" Dia. Gravity Sewer	LF	500			
0430.5311	Increase/Reduction of 0.059" Thickness for 30" Dia. Gravity Sewer	LF	500			
0430.7081	Increase/Reduction of 0.059" Thickness for 36" Dia. Gravity Sewer	LF	500			

SUB TOTAL SCHEDULE B

Total: Schedule A & Schedule B