



CITY OF TAMPA

Pam Iorio, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 4
DATE: May 11, 2007

Contract 7-C-7; Sidewalk Construction FY07

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

- Item 1: The Bid Opening Date for this project is hereby changed to May 22, 2007.
- Item 2: I-1.05 BASIS OF AWARD OF CONTRACT, add, after the last sentence, the following:
The actual amount to be awarded may be adjusted to suit funds available.
- Item 3: Add SP-9.11.1 DETECTABLE WARNING STRIPS ONLY
Detectable Warning Strips shall be installed at sidewalk intersection terminations that do not require pedestrian ramps. Installations shall adhere to the FDOT 2004 Interim Standards, Index 304.
Payment shall be made under: 522-3 Concrete Sidewalk 6" Min Thickness (No Ped Ramp) including detectable warning strips - S.Y.
- Item 4: Replace Pages P-3 and P-4 with P-3R and P-4R
- Item 5: SP-10.04 ROOT PRUNING, Replace the First Paragraph with the following:


The Contractor shall make provisions for tree protection to the satisfaction of the Engineer prior to any excavation or clearing and grubbing. All applicable site inspections by the City of Tampa Parks Department and all permits required for tree work shall be obtained by the Contractor prior to commencing work. The Contractor shall include in the permit application information about any pruning that will be done during the project.
- Item 6: SP-10.06 RESTORATION OF LANDSCAPING WITHIN THE RIGHT-OF-WAY

Replace the Second Paragraph with the following:

Cost of removing, restoring, relocating, and reconstructing the above items shall be included in the cost of the various contract items and no separate payment shall be made.
- Item 7: Disregard references to sidewalk locations on Bayshore Boulevard.

This addendum shall be included in and attached to the inside cover of the Contract Documents by and upon which bids are submitted. All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect.

Questions may be directed to Jim Greiner, P.E.; Telephone (813) 274-8598, fax (813) 274-8080, or e-mail Jim.Greiner@tampagov.net.



Jim Greiner, P.E., Contract Manager
Contract Administration Department

306 E. Jackson Street, 4N • Tampa, Florida 33602 • (813) 274-8456 • FAX: (813) 274-8080


www.tampagov.net

Contract 7-C-7; Sidewalk Construction FY07
 (Bayshore Blvd. and East Tampa)
 Project PW4888 and PW4707

Item No.	Description	Unit	Approx. Quantity	Unit Price in Words	Unit Price	Total Price
102-60	Work Zone Signs	E.D.	50	\$ _____	\$ _____	\$ _____
102-74-1	Barricades Type I or II	E.D.	2,500	\$ _____	\$ _____	\$ _____
120-2-2	Borrow Excavation	C.Y.	50	\$ _____	\$ _____	\$ _____
102-76	Arrow Board	E.D.	30	\$ _____	\$ _____	\$ _____
331-72-10	Type S Asphalt	Ton	1	\$ _____	\$ _____	\$ _____
400-1	Class I Concrete	C.Y.	25	\$ _____	\$ _____	\$ _____
515 -1	Aluminum Handrail FDOT Index 870 - 2 Rail	L.F.	60	\$ _____	\$ _____	\$ _____
515 - 2	Aluminum Handrail FDOT Index 860 - Picket	L.F.	60	\$ _____	\$ _____	\$ _____
520-2-4	Concrete Curb Type D	L.F.	100	\$ _____	\$ _____	\$ _____
522-1	Concrete S/W 4" Min Thickness	S.Y.	2,750	\$ _____	\$ _____	\$ _____
522-2	Concrete S/W 6" Min Thickness	S.Y.	1,000	\$ _____	\$ _____	\$ _____
522-3	Concrete S/W 6" Min Th. Ped Ramp incl. detectable Warning Strips	S.Y.	400	\$ _____	\$ _____	\$ _____
522-4	Concrete S/W 6" Min Th. No Ped Ramp incl. detectable Warning Strips	S.Y.	400	\$ _____	\$ _____	\$ _____
575-1-1	Solid Sod (Bahia)	S.Y.	1,000	\$ _____	\$ _____	\$ _____
575-1-4	Solid Sod (St. Augustine)	S.Y.	2,000	\$ _____	\$ _____	\$ _____
SP-9.05-1	Removal Existing Sidewalk	S.Y.	100	\$ _____	\$ _____	\$ _____
SP-9.05-2	Removal Existing Curb and Gutter	L.F.	100	\$ _____	\$ _____	\$ _____

Contract 7-C-7, Sidewalk Construction FY07
 (Bayshore Blvd. and East Tampa)
 Project PW4888 and PW4707

Item No.	Description	Unit	Approx. Quantity	Unit Price in Words	Unit Price	Total Price
SP-9.05-3	Extra Saw Cutting	L.F.	100	\$ _____	\$ _____	\$ _____
SP -10.02-6	Tree Removal >6" to 12" Diameter	EA	2	\$ _____	\$ _____	\$ _____
SP -10.02-12	Tree Removal >12" to 18" Diameter	EA	5	\$ _____	\$ _____	\$ _____
SP-10.04	Tree Root Pruning	L.F.	100	\$ _____	\$ _____	\$ _____
SP-10.04.1	Root Barrier	L.F.	100	\$ _____	\$ _____	\$ _____
SP-119	Contingency Allowance	L.S.	1	Twenty Thousand Dollars	20,000.00	\$ 20,000.00
TOTALS				\$ _____	\$ _____	\$ _____