



Contract Administration Michael W. Chucran, Director

306 East Jackson Street, 4N Tampa, FL 33602

> Office (813) 274-8116 Fax: (813) 274-7368

ADDENDUM 2 Via E-Mail DATE: November 10, 2021

Contract: 21-C-00037; Floribraska Gravity Sewer Rehabilitation by CIPP

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: Replace Proposal page P-2 with the attached Proposal page P-2R.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to Contract Administration@tampagov.net.

Jim Gr<u>einer</u>

Jim Greiner, P.E., Contract Management Supervisor

Contract; 21-C- 00037 Floribraska Gravity Sewer Rehabilitation by CIPP Lining

| literre Nie | Description | 11 | Approx. Quantity | Linit Drive in Words | Unit Drice | Tatal |
|-----------------|---|------------|---------------------|---|---------------------------|----------------------|
| Item No. 100 | Description Contingency | Unit LS | Quantity 1 | Unit Price in Words fifty thousand dollars | Unit Price \$50,000.00 | Total \$50,000.00 |
| 102 | Maintenance of Traffic | LS | 1 | | | |
| 0408.2360 | Cured in Place Pipe for 8" Dia. Gravity Sewer (.236 inch thick) | LF | 14,044 | | | |
| | Cured in Place Pipe for 10" Dia. Gravity Sewer (.295 inch thick) | LF | 368 | | | |
| 0412.2950 | Cured in Place Pipe for 12" Dia. Gravity Sewer (.295 inch thick) | LF | 952 | | | |
| 0416.2950 | Cured in Place Pipe for 16" Dia. Gravity Sewer (.295 inch thick) | LF | 12 | | | |
| 0418.2950 | Cured in Place Pipe for 18" Dia. Gravity Sewer (.354 inch thick) | LF | 10 | | | |
| 0421.4130 | Cured in Place Pipe for 21" Dia. Gravity Sewer (.413 inch thick) | LF | 61 | | | |
| 0601.08 | Hydraulic Cleaning & Inspection of 8" Dia. Gravity Sewer | LF | 14,044 | | | |
| 0601.10 | Hydraulic Cleaning & Inspection of 10" Dia. Gravity Sewer | LF | 368 | | | |
| 0601.12 | Hydraulic Cleaning & Inspection of 12" Dia. Gravity Sewer | LF | 952 | | | |
| 0601.16 | Hydraulic Cleaning & Inspection of 16" Dia. Gravity Sewer | LF | 12 | | | |
| 0601.18 | Hydraulic Cleaning & Inspection of 18" Dia. Gravity Sewer | LF | 10 | | | |
| 0601.21 | Hydraulic Cleaning & Inspection of 21" Dia. Gravity Sewer | LF | 61 | | | |
| 0602.08 | Additional Mechanical Cleaning & Inspection of 8" Dia. Gravity Sewer | LF | 1,000 | | | |
| 0622 | Cleaning & Inspection of Tuberculated Cast Iron or Ductile Iron Sewer, 16" Dia. & greater | LF | 12 | | | |
| 0700 | Disposal of Debris | CY | 40 | | | |
| 2050 | Reconnect Service Connections | EA | 316 | | | |
| 2051 | Chemical Grout Unit - chemical grout lateral post liner install | EA | 316 | | | |
| 2052 | Removal of Protruding Services | EA | 1 | | | |
| 4600.1p | Small Size manhole frame and cover replacement (in pavement) | EA | 10 | | | |
| 4800 | Manhole Rehabilitation by Coating System min. 250 mils thickness | SF | 4,768 | | | |
| 9000 | Sewer Bypass with Tanker Truck | Hrs | 10 | | | |
| 9050.08 | Sewage Bypass Pumping for 8" Dia. Sewer | LF | 14,044 | | | |
| 9050.10 | Sewage Bypass Pumping for 10" Dia. Sewer | LF | 368 | | | |
| 9050.12 | Sewage Bypass Pumping for 12" Dia. Sewer | LF | 10 | | | |
| 9050.12 | Sewage Bypass Pumping for 16", 18", and 21" Dia. Sewer | LF | 83 | | | |
| | | | | | TOTAL | |