21-C-00026; Virginia Park Wastewater Collection System Rehabilitation by CIPP
Bid Opening: 1:30P.M., November 16, 2021

			Approx.	Insistuform Technologies, LLC		LMR Construction Inc.		Miller Pipeline, LLC		Granite Inliner, LLC		Vortex Services, LLC	
Item No.	**Description**	**Unit**	**Quantity**	**Unit Price**	**Total**	**Unit Price**	**Total**	**Unit Price**	**Total**	**Unit Price**	**Total**	**Unit Price**	**Total**
100	Contingency	LS	1	$ 100,000.00	$100,000.00	$ 100,000.00	$100,000.00	$ 100,000.00	$100,000.00	$ 100,000.00	$100,000.00	$ 100,000.00	$100,000.00
102	Maintenance of Traffic	LS	1	$ 148,017.60	$148,017.60	$ 134,000.00	$134,000.00	$ 75,000.00	$75,000.00	$ 20,000.00	$20,000.00	$ 225,000.00	$225,000.00
0408.236	Cured in Place Pipe for 8" Dia. Gravity Sewer (.236 inch thick)	LF	46777	$ 21.09	$986,526.93	$ 25.00	$1,169,425.00	$ 22.75	$1,064,176.75	$ 28.00	$1,309,756.00	$ 29.50	$1,379,921.50
0410.295	Cured in Place Pipe for 10" Dia. Gravity Sewer (.295 inch thick)	LF	3460	$ 28.70	$99,302.00	$ 30.00	$103,800.00	$ 23.25	$80,445.00	$ 45.00	$155,700.00	$ 37.00	$128,020.00
0412.295	Cured in Place Pipe for 12" Dia. Gravity Sewer (.295 inch thick)	LF	257	$ 35.50	$9,123.50	$ 40.00	$10,280.00	$ 29.00	$7,453.00	$ 50.00	$12,850.00	$ 57.00	$14,649.00
0415.295	Cured in Place Pipe for 15" Dia. Gravity Sewer (.295 inch thick)	LF	1561	$ 46.30	$72,274.30	$ 55.00	$85,855.00	$ 60.30	$94,128.30	$ 70.00	$109,270.00	$ 60.00	$93,660.00
0424.472	Cured in Place Pipe for 24" Dia. Gravity Sewer (.472 inch thick)	LF	2381	$ 95.60	$227,623.60	$ 91.00	$216,671.00	$ 96.50	$229,766.50	$ 80.00	$190,480.00	$ 100.00	$238,100.00
0601.08	Hydraulic Cleaning & Inspection of 8" Dia. Gravity Sewer	LF	46527	$ 1.90	$88,401.30	$ 2.10	$97,706.70	$ 1.95	$90,727.65	$ 2.00	$93,054.00	$ 2.50	$116,317.50
0601.10	Hydraulic Cleaning & Inspection of 10" Dia. Gravity Sewer	LF	3360	$ 1.90	$6,384.00	$ 2.20	$7,392.00	$ 1.95	$6,552.00	$ 2.00	$6,720.00	$ 3.00	$10,080.00
0601.12	Hydraulic Cleaning & Inspection of 12" Dia. Gravity Sewer	LF	257	$ 1.90	$488.30	$ 2.40	$616.80	$ 1.95	$501.15	$ 2.00	$514.00	$ 6.50	$1,670.50
0601.15	Hydraulic Cleaning & Inspection of 15" Dia. Gravity Sewer	LF	1561	$ 4.20	$6,556.20	$ 5.30	$8,273.30	$ 2.70	$4,214.70	$ 3.00	$4,683.00	$ 4.50	$7,024.50
0601.24	Hydraulic Cleaning & Inspection of 24" Dia. Gravity Sewer	LF	2,381	$ 5.80	$13,809.80	$ 10.60	$25,238.60	$ 5.45	$12,976.45	$ 4.50	$10,714.50	$ 5.50	$13,095.50
0621	Cleaning & Inspection of Tuberculated Cast Iron or Ductile Iron Sewer , 8" Dia.	LF	250	$ 13.80	$3,450.00	$ 14.80	$3,700.00	$ 27.50	$6,875.00	$ 15.00	$3,750.00	$ 15.00	$3,750.00
0621	Cleaning & Inspection of Tuberculated Cast Iron or Ductile Iron Sewer , 10" Dia.	LF	100	$ 13.80	$1,380.00	$ 15.90	$1,590.00	$ 27.50	$2,750.00	$ 16.00	$1,600.00	$ 20.00	$2,000.00
0602.08	Additional Mechanical Cleaning & Inspection of 8" Dia. Gravity Sewer	LF	12,000	$ 3.20	$38,400.00	$ 5.00	$60,000.00	$ 5.00	$60,000.00	$ 4.50	$54,000.00	$ 6.00	$72,000.00
0602.10	Additional Mechanical Cleaning & Inspection of 10" Dia. Gravity Sewer	LF	850	$ 3.20	$2,720.00	$ 5.00	$4,250.00	$ 5.00	$4,250.00	$ 4.50	$3,825.00	$ 9.00	$7,650.00
0602.12	Additional Mechanical Cleaning & Inspection of 12" Dia. Gravity Sewer	LF	10	$ 3.20	$32.00	$ 6.00	$60.00	$ 9.90	$99.00	$ 4.50	$45.00	$ 25.00	$250.00
0602.15	Additional Mechanical Cleaning & Inspection of 15" Dia. Gravity Sewer	LF	250	$ 5.30	$1,325.00	$ 7.50	$1,875.00	$ 9.90	$2,475.00	$ 4.50	$1,125.00	$ 15.00	$3,750.00
0602.24	Additional Mechanical Cleaning & Inspection of 24" Dia. Gravity Sewer	LF	100	$ 9.50	$950.00	$ 12.30	$1,230.00	$ 9.90	$990.00	$ 4.50	$450.00	$ 25.00	$2,500.00
0700	Disposal of Debris	CY	70	$ 10.60	$742.00	$ 105.90	$7,413.00	$ 0.10	$7.00	$ 55.00	$3,850.00	$ 150.00	$10,500.00
2050	Reconnect Service Connections	EA	1,680	$ 50.00	$84,000.00	$ 0.01	$16.80	$ 100.00	$168,000.00	$ 50.00	$84,000.00	$ 1.00	$1,680.00
2051.08	Chemical Grouting Lateral after Lining in 8" Gravity Sewer	EA	1,100	$ 269.60	$296,560.00	$ 350.00	$385,000.00 *	$ 270.00	$297,000.00	$ 185.00	$203,500.00	$ 340.00	$374,000.00
2051.10	Chemical Grouting Lateral after Lining in 10" Gravity Sewer	EA	255	$ 269.60	$68,748.00	$ 100.00	$25,500.00	$ 250.00	$63,750.00	$ 185.00	$47,175.00	$ 340.00	$86,700.00
2051.12	Chemical Grouting Lateral after Lining in 12" Gravity Sewer	EA	2	$ 269.60	$539.20	$ 500.00	$1,000.00	$ 270.00	$540.00	$ 185.00	$370.00	$ 340.00	$680.00
2051.15	Chemical Grouting Lateral after Lining in 15" Gravity Sewer	EA	268	$ 269.60	$72,252.80	$ 100.00	$26,800.00	$ 275.00	$73,700.00	$ 185.00	$49,580.00	$ 340.00	$91,120.00
2051.24	Chemical Grouting Lateral after Lining in 24" Gravity Sewer	EA	55	$ 337.10	$18,540.50	$ 500.00	$27,500.00	$ 400.00	$22,000.00	$ 600.00	$33,000.00	$ 370.00	$20,350.00
4800	Manhole Rehabilitation by Coating System min. 250 mils thickness	SF	18,850	$ 28.60	$539,110.00	$ 26.00	$490,100.00	$ 29.70	$559,845.00	$ 30.00	$565,500.00	$ 29.00	$546,650.00
4600.1p	Small Size manhole frame and cover replacement (in pavement)	EA	120	$ 1,004.90	$120,588.00	$ 1,300.00	$156,000.00	$ 1,155.00	$138,600.00	$ 1,175.00	$141,000.00	$ 1,120.00	$134,400.00
9000	Sewer Bypass with Tanker Truck	HRS	80	$ 148.30	$11,864.00	$ 165.00	$13,200.00	$ 247.50	$19,800.00	$ 290.00	$23,200.00	$ 200.00	$16,000.00
9050.08	Sewage Bypass Pumping for 8" Dia. Sewer	LF	46,777	$ 0.05	$2,338.85	$ 0.05	$2,338.85	$ 0.05	$2,338.85	$ 1.40	$65,487.80	$ 0.25	$11,694.25
9050.10	Sewage Bypass Pumping for 10" Dia. Sewer	LF	3,460	$ 0.10	$346.00	$ 0.05	$173.00	$ 0.05	$173.00	$ 1.50	$5,190.00	$ 1.00	$3,460.00
9050.12	Sewage Bypass Pumping for 12" Dia. Sewer	LF	257	$ 3.20	$822.40	$ 0.05	$12.85	$ 0.05	$12.85	$ 1.50	$385.50	$ 15.00	$3,855.00
9050.15	Sewage Bypass Pumping for 15" Dia. Sewer	LF	1,561	$ 5.30	$8,273.30	$ 2.00	$3,122.00	$ 5.50	$8,585.50	$ 21.50	$33,561.50	$ 15.00	$23,415.00
9050.24	Sewage Bypass Pumping for 24" Dia. Sewer	LF	2,381	$ 19.10	$45,477.10	$ 11.00	$26,191.00	$ 27.50	$65,477.50	$ 50.00	$119,050.00	$ 15.00	$35,715.00
				TOTAL	**$3,076,966.68**	**TOTAL**	**$3,196,330.90** *	**TOTAL**	**$3,263,210.20**	**TOTAL**	**$3,453,386.30**	**TOTAL**	**$3,779,657.75**

*Arithmetic correction by Contract Administration

Notice of Intent to Award: Unless subsequently indicated otherwise, in a revised posting, the City of Tampa intends to award the referenced project to the lowest bidder listed in this tabulation. A bidder aggrieved by this decision may file a protest not later than 4:30 P.M., five (5) business days from the first posting hereof, pursuant to City of Tampa Code Chapter 2, Article V, Division 3, Section 2-282, Procurement Protest Procedures. Protests not conforming therewith shall not be reviewed.

Bids Received By: Jim Greiner

Jim Greiner, P.E.
City of Tampa - Contract Administration Department
306 E. Jackson Street - 4N
Tampa, FL 33602