



CITY OF TAMPA

Bob Buckhorn, Mayor

Contract Administration Department

Michael W. Chucran, Director

ADDENDUM 4

October 30, 2018

Contract 18-C-00041; Stormwater Construction Citywide FY18

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: Replace existing pages P-2, P-3 and P-4 with the attached pages P-2R, P-3R and P-4R.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to ContractAdministration@tampagov.net.

Jim Greiner

Jim Greiner, P.E. Contract Management Supervisor

| Item No. | Description | Unit | Est Qty | Unit Price in Words | Unit Price | Total Price |
|----------|--|------|---------|---------------------|------------|-------------|
| 105.2B | TREE REMOVAL - 9"-18" | EA | 22 | | \$ | \$ |
| 110.1 | CLEARING & GRUBBING POND SITE | AC | 2 | | \$ | \$ |
| 120 | REGULAR EXCAVATION AND DISPOSAL | CY | 2,100 | | \$ | \$ |
| 130 | CLEAN FILL | CY | 7,600 | | \$ | \$ |
| 135 | GRADE DITCH | LF | 85 | | \$ | \$ |
| 110.3 | GROUT EX. STORMWATER PIPE LATERALS | CY | 10 | | \$ | \$ |
| 425.1 | INLETS, DT BOT, TYPE E, <10' | EA | 15 | | \$ | \$ |
| 425.2 | MANHOLES, P-7, <10' deep (3.5') | EA | 12 | | \$ | \$ |
| 425.3 | MANHOLES, J-7, <10' deep (4') | EA | 3 | | \$ | \$ |
| 425.4 | INLET, COT CURB TYPE 1, <10' | EA | 1 | | \$ | \$ |
| 425.5.2 | INLET, COT CURB TYPE 2, MODIFIED TYPE H BOTTOM | EA | 1 | | \$ | \$ |
| 425.7 | INLET, COT CURB TYPE BR-1, <10' | EA | 1 | | \$ | \$ |
| 425.8 | INLET, COT GRATE TYPE T, <10' | EA | 47 | | \$ | \$ |
| 430.15 | 15" ROUND STORMWATER PIPE (RCP) | LF | 1,200 | | \$ | \$ |
| 430.1 | 18" ROUND STORMWATER PIPE (RCP) | LF | 1,000 | | \$ | \$ |
| 430.11 | 19"x30" MITERED END SECTION | EA | 3 | | \$ | \$ |
| 430.12A | CONNECT STORMWATER PIPE TO EXISTING STRUCTURE (0-24") | EA | 18 | | \$ | \$ |
| 430.12B | CONNECT STORMWATER PIPE TO EXISTING STRUCTURE (30-60") | EA | 1 | | \$ | \$ |
| 430.2 | 24" ROUND STORMWATER PIPE (RCP) | LF | 500 | | \$ | \$ |
| 430.30A | 30" ROUND STORMWATER PIPE (RCP) | LF | 400 | | \$ | \$ |
| 430.60A | 60" ROUND STORMWATER PIPE (RCP) | LF | 100 | | \$ | \$ |
| 430.4 | 12"x18" ELLIPTICAL STORMWATER PIPE (CLASS IV) (RCP) | LF | 1,093 | | \$ | \$ |

| Item No. | Description | Unit | Est Qty | Unit Price in Words | Unit Price | Total Price |
|----------|---|------|---------|---------------------|------------|-------------|
| 430.5 | 14"x23" ELLIPTICAL STORMWATER PIPE (ERCP) | LF | 299 | | \$ | \$ |
| 430.6 | 19"x30" ELLIPTICAL STORMWATER PIPE (ERCP) | LF | 1,298 | | \$ | \$ |
| 530 | Rip Rap - (2' deep) | CY | 89 | | \$ | \$ |
| 550.1 | REMOVE AND RESET FENCE | LF | 1,255 | | \$ | \$ |
| 8901 | SOD - AUGUSTINE | SY | 9,500 | | \$ | \$ |
| 8902 | SOD - BAHIA | SY | 8,056 | | \$ | \$ |
| 8903 | Hydroseeding | SY | 2,900 | | \$ | \$ |
| 285.2 | BEDDING | TN | 237 | | \$ | \$ |
| 334 | SUPERPAVE ASPHALTIC CONC, SP12.5 (2") | TN | 936 | | \$ | \$ |
| 520.6 | F&I Type "D" concrete curb | LF | 100 | | \$ | \$ |
| 520.8 | F&I CURB, DROP | LF | 130 | | \$ | \$ |
| 520.110 | CONCRETE CURB AND GUTTER TYPE "F" | LF | 785 | | \$ | \$ |
| 522.1 | SIDEWALK CONCRETE, 6" THICK (3000 psi) | SY | 573 | | \$ | \$ |
| 522.2 | CONCRETE, 6" THICK (DRIVEWAYS) (3000psi) | SY | 2,586 | | \$ | \$ |
| 9250 | ADA Compliant Ramps | EA | 25 | | \$ | \$ |
| 2103 | F&I 8" ductile iron pipe offset - all inclusive with tap (<30' in length) | EA | 1 | | \$ | \$ |
| 2103.12 | F&I 12" ductile iron pipe offset - all inclusive with tap (<30' in length) | EA | 2 | | \$ | \$ |
| 2106 | F&I 10" DIP - polywrap w fittings and restraints - all inclusive | LF | 3,040 | | \$ | \$ |
| 2107.PS | Installation of Flygt pump, control panel, floats and internal piping (for stormwater pump station, pump and electrical panel materials provided by City) | LS | 1 | | \$ | \$ |
| 2200 | F&I 2" HDPE tubing by HDD w/HDPE adapters and HDPE fittings at various depths - all inclusive with tap (20' in length) | EA | 2 | | \$ | \$ |
| 6004 | F&I 10" gate or tapping valve with box on DIP, CIP or PVC | EA | 6 | | \$ | \$ |

| Item No. | Description | Unit | Est Qty | Unit Price in Words | Unit Price | Total Price |
|----------|--|------|---------|---------------------|------------|---------------|
| 6005 | F&I 10" air release valve | EA | 2 | | \$ | \$ |
| 6104 | F&I 8" Linestop on Existing Water Main | EA | 1 | | \$ | \$ |
| 900.1 | 8" Dia. PVC Pipe (C-900, DR-18) | LF | 25 | | \$ | \$ |
| 900.2 | 24" Dia. PVC Pipe (C-900, DR-18) | LF | 20 | | \$ | \$ |
| 1706 | 6-Inch Diameter PVC Pipe House Lateral (SDR-35) (<30' in length) | EA | 25 | | \$ | \$ |
| 1707 | 6" Dia. PVC Pipe (SDR-26) | LF | 30 | | \$ | \$ |
| 1708 | 8" Dia. PVC Pipe (SDR-26) | LF | 80 | | \$ | \$ |
| 1709 | 10" Dia. PVC Pipe (SDR-26) | LF | 20 | | \$ | \$ |
| 4660 | 6-Inch Diameter, SDR-35, PVC Clean-out and cover | EA | 25 | | \$ | \$ |
| 100 | CONTINGENCY | LS | 1 | | \$ 250,000 | \$ 250,000.00 |
| | | | | Sub Total | | |
| 101 | MOBILIZATION - 8% of Subtotal | LS | 1 | | \$ | \$ |
| 102 | MAINTENANCE OF TRAFFIC - 10% of Subtotal | LS | 1 | | \$ | \$ |
| | | | | Total | | |