



CITY OF TAMPA

Bob Buckhorn, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

Michael W. Chucran, Director

ADDENDUM 4

DATE: January 18, 2019

Contract 19-C-00013; Lowry Park and Davis Island Seaplane Basin Park Dock Improvements

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: The Bid Opening date for this project is hereby changed to January 29, 2019

Item 2: Replace Proposal pages P-2 and P-3 with the attached Proposal pages P-2R and P-3R.

Item 3: Clarification - Lowry Park plan sheet S-100; the concrete slab repair scope is to saw cut the perimeter of the damaged area, remove the cracked and damaged concrete, and provide cast-in-place concrete to replace the damaged areas.

Item 4: - Davis Island plan sheet G-003, Concrete Work quantity table, right side column: Change "(CY)" to "(CF)".

Item 5: Clarification - The dock/boardwalk hardware and fasteners as detailed in the plans and specifications indicate where stainless steel is to be used.

At the Lowry Park timber docks, stainless steel shall be used for all miscellaneous metals and hardware below the deck elevation and for connection of railings, rub strips, ladders, cleats, signs, warning lights, pile wraps, etc. The Lowry Park bulkhead tie rods shall be Hot Dip Galvanized.

At the Davis Island floating docks, if through rods are used with timber wales, the through rods and hardware shall be Stainless steel.

Item 6: Clarification - For the Lowry Park south dock bulkhead, Lowry Park plan sheet S-401 Detail B1; the top of pile cap elevation is +3.5-ft, the tip elevation of the sheet piles shall be -10.0 ft NAVD, minimum. The length of the bulkhead is shown in Lowry Park plan sheet S-100.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to Contract Administration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor

19-C-00013 Lowry Park and Davis Island Seaplane Basin Park Dock Improvements

Contract Item No.	Estimated Quantity	Description and Price in Words	Computed Total Price for Item in Figures
BASE BID	LS	<p>The work comprises the furnishing of all labor, equipment, and material for the replacement of the docks at Davis Islands Seaplane Basin Park including dredging and demolition of existing docks, landside sidewalks, piles and installation of all new materials and required signage, a \$35,000 allowance as listed in SP - 60, and with all associated work required for a complete project in accordance with the Contract Documents.</p>	<p>_____ dollars and _____ cents LS \$ _____</p>
ALTERNATE No. 1	LS	<p>The work comprises the furnishing of all labor, equipment, and material for the replacement of the boardwalks at Lowry Park including demolition of existing, boardwalk, landside sidewalks, piles and installation of all new materials and required signage, a \$20,000 allowance as listed in SP - 60, and with all associated work required for a complete project in accordance with the Contract Documents.</p>	<p>_____ dollars and _____ cents LS \$ _____</p>

19-C-00013 Lowry Park and Davis Island Seaplane Basin Park Dock Improvements

Contract Item No.	Estimated Quantity	Description and Price in Words	Computed Total Price for Item in Figures
ALTERNATE No. 2	LS	<p>The work comprises the furnishing of all labor, equipment, and material for the replacement of the Lowry Park North Dock including demolition of existing docks, landside sidewalks, piles and installation of all new materials and required signage, a \$20,000 allowance as listed in SP - 60, and with all associated work required for a complete project in accordance with the Contract Documents.</p>	<p>_____ dollars and _____ cents LS \$ _____</p>
ALTERNATE No. 3	LS	<p>The work comprises the furnishing of all labor, equipment, and material for the replacement of the Lowry Park South Dock including demolition of existing docks, landside sidewalks, piles, boat ramp concrete slab repair, sheet pile bulkhead, and installation of all new materials and required signage, a \$20,000 allowance as listed in SP - 60, and with all associated work required for a complete project in accordance with the Contract Documents.</p>	<p>_____ dollars and _____ cents LS \$ _____</p>