



CITY OF TAMPA

Bob Buckhorn, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

ADDENDUM NO. 1

DATE: May 24, 2013

Contract 13-C-00022; David L. Tippin Water Treatment Facility Bromate Control Project

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: The Bid Date for the above referenced project is hereby changed to June 11, 2013.

Item 2: RFI and Responses

RFI: Ref. Drawing E-2 Note #2. - Can you help me understand what "match all the control features provided for the existing units"? This will help me determine if new control hardware is going to be required as part of the GC/EC scope.

Response: The local control panel includes simple local controls as shown on the attached photo and defined in Specification 11390. Bidders are to familiarize themselves with the features provided for the existing units and match them.

RFI: Ref. Drawing E-3. - The drawing directs us to install a 60a breaker inside the existing MPZ but the conduit and cable size (3/4" and #10awg) is only rated for a 30a circuit. Should we decrease the size of the breaker or should we increase the size of the conduit and wire? It does appear that 30a will be more than sufficient.

Response: Revise wire size to be 2-#6, 1-#10G in 1" conduit.

RFI: Ref. Drawing E-3 Riser Diagram and the associated spec. - Is it the intent for the electrical subcontractor to provide and/or install and wire the analyzer building: lighting panel, interior and exterior lights and switches, receptacles, A/C unit, and UPS? Or should we plan on only including the power conduit and cable feeding the lighting panel and the control cables from the Ammonia Monochlorine analyzer to the PLC CP-60-1?

Response: The FRP building manufacturer shall provide and install/wire the indoor and outdoor lighting, receptacles, lighting panel enclosure, A/C unit and switches within the FRP building. The electrical subcontractor will be responsible for providing and installing power and control wiring to the building as well as providing and installing the UPS and analyzer. The electrical subcontractor and the FRP building supplier shall coordinate per Specification 13122.

306 E. Jackson Street, 4N • Tampa, Florida 33602 • (813) 274-8456 • FAX: (813) 274-8080



Item 3: Attached for your reference is the Pre-Bid sign-in sheet.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to [Contract Administration@tampagov.net](mailto:ContractAdministration@tampagov.net).

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor



AMMONIA

AMMONIA

AMMONIA

VALOR
4.2
WINDICE VALVE-TRONIC

VALOR
2.9
WINDICE VALVE-TRONIC

VELAN

VELAN

13-C-00022; David L. Tippin Water Treatment Facility Bromate Control - PreBid Meeting 10:00

E-Mail to Register as a Bidder and E-Mail All Questions to; ContractAdministration@tampagov.net

Sign-In Sheet Please Print

City of Tampa, Contract Administration Department

	Name	Organization	E-Mail OR Phone
1	Jody Gray	Tampa Contract Administration Dept.	jody.gray@tampagov.net
2	Greg Doan	TLC Diversified	gdoan@tlediversified.com
3	Morgan Don	RTD Construction	bids@rtdconstruction.com
4	Andre Dietzold	Hazen and Sawyer	adiet@hazenandsawyer.com
5	John Ranson	Tampa Water Dept	john.ranson@tampagov.net
6	Carlos ESTRADA	" "	Carlos.Estrada@Tampagov.net
7	ANDREW BARNETT	BARNETT SUPPLY	BARNETT.SUPPLY@VERIZON.NET
8	John Babuka	Reliable Electric	John@reliableelectricusa.com
9	FRANK WOODARD	COT CND	FRANK.WOODARD@TAMPAGOV.NET
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			