



# CITY OF TAMPA

Bob Buckhorn, Mayor

CONTRACT ADMINISTRATION DEPARTMENT

David L. Vaughn, AIA, Director

## ADDENDUM NO. 1 DATE: November 26, 2013

Contract 14-C-00010; Wastewater Collection System Repair-FY14

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

- Item 1: Replace Proposal pages P-3, P-6 and P-7 with the attached pages P-3R, P-6R and P-7R.
- Item 2: Specific Provisions, SP-27 Existing Public Facilities; delete "shelters" from this specific provision.
- Item 3: Workmanship and Materials Section 10 Ductile Iron Pipe and Fittings: Revise Section 10.03 Fittings to read: "All ductile iron fittings shall meet the requirements of AWWA C110 or C153, and have a pressure rating of 250 psi, or as specified, whichever is larger."
- Item 4: Workmanship and Materials Section 13 HDPE Pipe/Directional Drilling, Section 2.03 PIPE: Revise in Section 2.03 C. the first sentence to read: "HDPE pipe shall have a minimum SDR rating of 11."
- Item 5: Contract Item 0700 Series – Solid Wall PVC Pipe and Contract Item 0900 Series – PVC Pipe Sewer (Green AWWA CL. 150, C900): Revise the second paragraph to read: "The work includes all related work and appurtenances required to locate existing sanitary sewer lines and make the connections as shown on the plans to the proposed lines, alignment survey..."
- Item 6: Contract Item 1005 Series – Directional Drilled Pipe: Revise the second paragraph to read: "The work includes all related work and appurtenances required to construct new directional drilled HDPE force mains as shown on the plans or directed by the Engineer, including alignment survey..."
- Item 7: Contract Item 8100 Series – Permanent Pavement Surface Replacement: Revise the last paragraph to read: "Payment for Permanent Pavement Surface Replacement will be made at the Contract Item Unit Price per Ton of pavement surface replaced."
- Item 8: Attached for reference is the pre-bid sign-in sheet.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to [ContractAdministration@tampagov.net](mailto:ContractAdministration@tampagov.net).

*Jim Greiner*

Jim Greiner, P.E., Contract Management Supervisor

306 E. Jackson Street, 4N • Tampa, Florida 33602 • (813) 274-8456 • FAX: (813) 274-8080



| Item No.  | Description   | Unit | Approx.<br>Quantity | Unit Price in Words       | Unit Price   | Total Computed Price |
|-----------|---|------|---------------------|---------------------------|--------------|----------------------|
| *** 0101  | Mobilization  | L.S  | 1                   | Forty Thousand Dollars    | \$ 40,000.00 | \$ 40,000.00         |
| *** 0102  | Contingency   | LS   | 1                   | Fifty Thousand Dollars    | \$ 50,000.00 | \$ 50,000.00         |
| 0103      | Project Sign  | Ea   | 2                   |                           | \$           | \$                   |
| *** 0110  | Additional Earth Excavation                                 | C.Y. | 20                  | Four Dollars              | \$ 4.00      | \$ 80.00             |
| 0120      | Excavation for Restraining Device on Existing Force Main    | C.Y  | 4                   |                           | \$           | \$                   |
| *** 0130  | Additional Select Sand Fill                                 | C.Y. | 10                  | Ten Dollars               | \$ 10.00     | \$ 100.00            |
| *** 0140  | Additional Select Crushed Stone Material                    | C.Y. | 10                  | Thirty Dollars            | \$ 30.00     | \$ 300.00            |
| *** 0170  | Class D Concrete  | C.Y  | 5                   | One Hundred Sixty Dollars | \$ 160.00    | \$ 800.00            |
| 0200      | Short Tunnel  | L.F. | 10                  |                           | \$           | \$                   |
| 0520-1    | Standard Concrete Curb or Curb and Gutter                   | L.F  | 200                 |                           | \$           | \$                   |
| 0708.06   | 8-Inch Diameter, SDR-35, PVC Pipe Sewer in cuts 0 to 6 ft.  | L.F. | 5,500               |                           | \$           | \$                   |
| 0708.13   | 8-Inch Diameter, SDR-35, PVC Pipe Sewer in cuts 6 to 13 ft. | L.F. | 1,000               |                           | \$           | \$                   |
| 0900-4-06 | 4" Dia. C900 PVCP, CI-150, Green, 0'-6' Cut                 | L.F  | 1,000               |                           | \$           | \$                   |
| 0900-4-13 | 4" Dia. C900 PVCP, CI-150, Green, 6'-13' Cut                | L.F  | 500                 |                           | \$           | \$                   |
| 0900-6-06 | 6" Dia. C900 PVCP, CI-150, Green, 0'-6' Cut                 | L.F  | 5,500               |                           | \$           | \$                   |
| 0900-6-13 | 6" Dia. C900 PVCP, CI-150, Green, 6'-13' Cut                | L.F  | 1,000               |                           | \$           | \$                   |

| Item No. | Description  | Unit | Approx.<br>Quantity | Unit Price in Words | Unit Price | Total Computed Price |
|----------|--|------|---------------------|---------------------|------------|----------------------|
| 4700.8   | 8-inch Diameter PVC Pipe Manhole Drop Connection               | L.F. | 10                  |                     | \$         | \$                   |
| 4900     | Connect to Existing Manhole, no existing pipe                  | Ea   | 4                   |                     | \$         | \$                   |
| 5000     | Remove Existing Pipe 4" to 27" Diameter Outside of Pay Limits  | L.F. | 2,000               |                     | \$         | \$                   |
| 5051     | Filling of Existing Sanitary Sewers                            | C.Y  | 60                  |                     | \$         | \$                   |
| 7000.4   | 4" Dia. Plug Valve with Box                                    | Ea   | 4                   |                     | \$         | \$                   |
| 7000.6   | 6" Dia. Plug Valve with Box                                    | Ea   | 6                   |                     | \$         | \$                   |
| 7000.8   | 8" Dia. Plug Valve with Box                                    | Ea   | 4                   |                     | \$         | \$                   |
| 7000.12  | 12" Dia. Plug Valve with Box                                   | Ea   | 6                   |                     | \$         | \$                   |
| 7500     | Air Release Valve Assembly                                     | Ea   | 40                  |                     | \$         | \$                   |
| 8000     | Permanent Pavement Base (Crushed Limerock or Crushed Concrete) | C.Y  | 4,000               |                     | \$         | \$                   |
| 8100     | Permanent Asphalt Pavement Type S                              | TON  | 3,000               |                     | \$         | \$                   |
| 8100.1   | Permanent Asphalt Pavement Type Superpave (including testing)  | TON  | 150                 |                     | \$         | \$                   |
| 8306     | Permanent 6" Thick Concrete Driveway                           | S.Y  | 300                 |                     | \$         | \$                   |
| 8604     | Permanent 4" Thick Concrete Sidewalk                           | S.Y  | 800                 |                     | \$         | \$                   |
| 8900.2   | Bahia Sod  | S.Y  | 2,000               |                     | \$         | \$                   |
| 8900.3   | St.Augustine Sod   | S.Y  | 1,000               |                     | \$         | \$                   |
| 9000.1   | Force Main Sewage Bypass Piping, 6 to 8-inch                   | L.F  | 350                 |                     | \$         | \$                   |
| 9000.2   | Force Main Sewage Bypass Piping, 10 to 12-inch                 | L.F  | 350                 |                     | \$         | \$                   |
| 9100.4   | 4-inch Dia. Line Stop, 3 day max.                              | Ea   | 2                   |                     | \$         | \$                   |

| Item No.  | Description   | Unit    | Approx.<br>Quantity | Unit Price in Words  | Unit Price | Total Computed Price |
|-----------|---|---------|---------------------|----------------------|------------|----------------------|
| 9100.6    | 6-inch Dia. Line Stop, 3 day max.                           | Ea      | 2                   |                      | \$         | \$                   |
| 9100.8    | 8-inch Dia. Line Stop, 3 day max.                           | Ea      | 2                   |                      | \$         | \$                   |
| 9100.12   | 12-inch Dia. Line Stop, 3 day max.                          | Ea      | 2                   |                      | \$         | \$                   |
| 9200      | Root Pruning  | L.F     | 200                 |                      | \$         | \$                   |
| 9300      | Sawcut Asphalt or Concrete Pavement, Driveways or Sidewalks | L.F     | 500                 |                      | \$         | \$                   |
| 9400      | Mill Existing Asphalt Pavement, any quantity                | IN/S.Y. | 400                 |                      | \$         | \$                   |
| 10000.4   | Connections between 4" PVCP & HDPE                          | Ea      | 4                   |                      | \$         | \$                   |
| 10000.6   | Connections between 6" PVCP & HDPE                          | Ea      | 4                   |                      | \$         | \$                   |
| 10000.8   | Connections between 8" PVCP & HDPE                          | Ea      | 6                   |                      | \$         | \$                   |
| 10000.12  | Connections between 12" PVCP & HDPE                         | Ea      | 4                   |                      | \$         | \$                   |
| *** 20000 | As-Built Plans  | Sheet   | 16                  | Five Hundred Dollars | \$ 500.00  | \$ 8,000.00          |
|           |   |         |                     | TOTAL                | \$         | \$                   |
|           |   |         |                     |                      |            |                      |
|           |   |         |                     |                      |            |                      |
|           |   |         |                     |                      |            |                      |

CONTRACT 14-C-00010; WASTEWATER COLLECTION SYSTEM REPAIR FY14 - PRE-BID MTG. 11/19/2013

E-Mail to Register as a Plan Holder and E-Mail All Questions to: [ContractAdministration@tampagov.net](mailto:ContractAdministration@tampagov.net)

Sign-In Sheet ☐ Please Print

City of Tampa, Contract Administration Department

|    | Name            | Organization                        | E-Mail OR Phone              |
|----|-----------------|-------------------------------------|------------------------------|
| 1  | Jim Greiner, PE | Tampa Contract Administration Dept. | Jim.Greiner@tampagov.net     |
| 2  | Jody Gray       | C.O.T Contract Admin                | jody.gray@tampagov.net       |
| 3  | ANWAR AKHLAQ    | KIMMINS                             | aakhlag@kimmins.com          |
| 4  | Tom Secord      | Secord                              | tomsecord.us                 |
| 5  | Darel Young     | Bore Hawk Drilling                  |                              |
| 6  | Mike Keenach    | Holland Pump                        | mikek@hollandpump.com        |
| 7  | Joe Minich      | AJAX PAVING                         | jminich@ajaxpaving.com       |
| 8  | Brett Altman    | Ferguson Waterworks                 | brett.altman@ferguson.com    |
| 9  | Daniel Hech     | Cerrus Builders                     | dsumner@CerrusBuilders.com   |
| 10 | Rick Losiwiecki | WOODRUFF & SONS                     | Rick@WOODRUFFANDSONS.COM     |
| 11 | Ed Harris       | Dalles I construction               | Edo.Harris@DLCI.COM          |
| 12 | Cassidy Barrett | COT WW Design                       | Cassidy.Barrett@tampagov.net |
| 13 | JACK FERRAS     | COT WW DESIGN                       | JACK.FERRAS@TAMPAGOV.NET     |
| 14 | Amy Blachwelder | TB Landmark Construction            | amyb@tlandmark.com           |
| 15 | BRIAN BIXLER    | SHALE INLAND PUF                    | BRIAN.BIXLER@SHALEINLAND.COM |
| 16 |                 |                                     |                              |
| 17 |                 |                                     |                              |
| 18 |                 |                                     |                              |
| 19 |                 |                                     |                              |
| 20 |                 |                                     |                              |
| 21 |                 |                                     |                              |
| 22 |                 |                                     |                              |
| 23 |                 |                                     |                              |
| 24 |                 |                                     |                              |
| 25 |                 |                                     |                              |
| 26 |                 |                                     |                              |
| 27 |                 |                                     |                              |
| 28 |                 |                                     |                              |
| 29 |                 |                                     |                              |
| 30 |                 |                                     |                              |
| 31 |                 |                                     |                              |
| 32 |                 |                                     |                              |
| 33 |                 |                                     |                              |
| 34 |                 |                                     |                              |
| 35 |                 |                                     |                              |
| 36 |                 |                                     |                              |