



City of Tampa

Jane Castor, Mayor

Contract Administration

Michael W. Chucran, Director

306 East Jackson Street, 4N
Tampa, FL 33602

Office (813) 274-8116

Fax: (813) 274-7368

ADDENDUM 1

Via E-Mail

DATE: April 17, 2020

Contract 20-C-00031; Westshore Blvd Collection System CIPP Lining

Bidders on the above referenced project are hereby notified that the following addendum is made to the Contract Documents. BIDS TO BE SUBMITTED SHALL CONFORM TO THIS NOTICE.

Item 1: The Bid Opening Date is hereby changed to April 28, 2020.

Item 2: A method for conducting public bid openings during the current conditions is being developed. It is likely to require that all bids be submitted by USPS or parcel delivery service. It is also likely that the public opening process will be conducted with online accessibility. Instructions will be included in a subsequently issued addendum.

Item 3: Replace proposal page P-2 with the attached proposal page P-2R.

Item 4: Insert the attached Contract Item 0630 Series.

All other provisions of the Contract Documents and Specifications not in conflict with this Addendum shall remain in full force and effect. Questions are to be e-mailed to Contract Administration@tampagov.net.

Jim Greiner

Jim Greiner, P.E., Contract Management Supervisor

20-C- 00031 Westshore Blvd Collection System CIPP Lining					
Item No.	Description	Unit	Approx. Quantity	Unit Price	Total
100	Contingency	LS	1	\$100,000.00	\$100,000.00
102	Maintenance of Traffic	LS	1		
0408.2360	Cured in Place Pipe for 8" Dia. Gravity Sewer (.236 inch thick)	LF	13,123		
0410.2950	Cured in Place Pipe for 10" Dia. Gravity Sewer (.295 inch thick)	LF	1,661		
0415.2950	Cured in Place Pipe for 15" Dia. Gravity Sewer (.295 inch thick)	LF	1,187		
0418.3540	Cured in Place Pipe for 18" Dia. Gravity Sewer (.354 inch thick)	LF	4,148		
0601.08	Hydraulic Cleaning & Inspection of 8" Dia. Gravity Sewer	LF	13,123		
0601.10	Hydraulic Cleaning & Inspection of 10" Dia. Gravity Sewer	LF	1,661		
0601.15	Hydraulic Cleaning & Inspection of 15" Dia. Gravity Sewer	LF	1,187		
0601.18	Hydraulic Cleaning & Inspection of 18" Dia. Gravity Sewer	LF	4,148		
0621	Cleaning & Inspection of Tuberculated Cast Iron or Ductile Iron Sewer, 8" Dia.	LF	295		
621.1	Cleaning & Inspection of Tuberculated Cast Iron or Ductile Iron Sewer, 10" Dia.	LF	41		
630	Cleaning & Inspection of Gravity Sewer Laterals (Along West Shore Blvd)	LF	2,800		
0700	Disposal of Debris	CY	55		
2050	Reconnect Service Connections	EA	311		
2051	Chemical Grouting Lateral after Lining	EA	311		
4800	Manhole Rehabilitation by Coating System min. 250 mils thickness	SF	7,200		
9000	Sewer Bypass with Tanker Truck	Hrs	640		
9050.08	Sewage Bypass Pumping for 8" Dia. Sewer	LF	13,123		
9050.10	Sewage Bypass Pumping for 10" Dia. Sewer	LF	1,661		
9050.15	Sewage Bypass Pumping for 15" Dia. Sewer	LF	1,187		
9050.18	Sewage Bypass Pumping for 18" Dia. Sewer	LF	4,148		

P-2R

CONTRACT ITEM 0630 SERIES - CLEANING AND INSPECTION
OF GRAVITY SEWER LATERALS (WEST SHORE BLVD)

The Contractor shall furnish all labor, materials, and equipment to provide cleaning and inspection of the existing gravity sewer laterals along West Shore Boulevard from W. San Rafael Street to W. Longfellow Avenue. Hydraulic cleaning requires use of standard water jet equipment regardless of the number of passes required or cleaning by mechanical means. Cleaning includes all dirt, grease and sludge removal from the existing sewer lateral to facilitate the TV inspection.

The work includes furnishing all related work to provide cleaning of the existing sewer laterals and inspecting the cleaned sewer laterals with a lateral launch closed circuit camera from within the sewer main.

Measurement for payment will be the actual length of pipe cleaned and inspected. Payment for Cleaning and Inspection will be made at the appropriate Contract Item Unit Price per linear foot. There are approximately (70) laterals of varying lengths along West Shore Boulevard from W. San Rafael Street to W. Longfellow Avenue with a total of (2800) linear feet.