



Eric Fetrow
 306 E. Jackson Street Tampa FL 33602
 813-274-7954

Specs By Location

4/6/2017

Owner's Name

Owner's Phone #

Address: 10923 N 21st Street **Unit: Unit 01**

Location: 1 - General Requirements Approx. Wall SF: 0 Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 1	General Requirements				
1	10 OWNER ACCEPTS SCOPE OF WORK The undersigned applicant(s) certifies that he/she has participated in the development of this Scope of Work Write Up (SWWU) with the "Date inspected" date of _____ & referred to as Exhibit 1. After careful review the applicant understands & accepts the work described & has initialed & dated each page of this SWWU. X _____ X _____ Applicant Date Applicant Date	1.00	DU	_____	_____
2	14 CONTRACTOR ACCEPTS SCOPE OF WORK The undersigned contractor certifies that he/she has carefully reviewed & agrees to perform the work described in this Scope of Work Write Up (SWWU) with the "Date Inspected" date of _____ & referred to as Exhibit 1. The contractor shall initial & date each page of the SWWU. X _____ Contractor Date	1.00	DU	_____	_____
3	31 CONSTRUCTION DEFINITIONS "Install" means to purchase, set up, test and warrant a new component. " Replace" means to remove and dispose of original material, purchase new material, deliver, install, test and warrant. "Repair" means to return a building component to like new condition through replacement, adjustment and recoating of parts. "Reinstall" means to remove, clean, store and install a component.	1.00	GR	_____	_____
4	32 SUBSTITUTION APPROVAL PROCESS Any requests for substitutions of specified proprietary items must accompany the initial proposal and shall include: the manufacturer's specifications; full installation instructions and warranties. The agency and owner will notify the contractor of decision at contract award.	1.00	GR	_____	_____
5	35 VERIFY QUANTITIES/MEASUREMENTS All Quantities stated in the attached specifications for this address using Units of Measure other than Each (EA), Room (RM) or Dwelling Unit (DU) (e.g. SF of Drywall) are for the contractor's convenience and must be verified by the contractor at a mandatory site inspection prior to bid submission. All quantities stated in the Units of Measure Each (EA), Room (RM) or Dwelling Unit (DU) are as stated. Discrepancies in Quantities found by the contractor must be communicated to the Housing Rehabilitation Specialist prior to the submission of a bid. Claims for additional funds due to discrepancies in Quantities shall not be honored if submitted after the bid submission.	1.00	GR	_____	_____
6	40 ALL PERMITS REQUIRED	1.00	AL	_____	_____

Location: 1 - General Requirements

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 1	General Requirements				
	Contractor shall apply for and get all permits necessary for all Scope of Work Write Up (SWWU).				
7	45 CONTRACTOR PRE-BID SITE VISIT The contractor must inspect the property. Submission of a bid is presumptive evidence that the bidder has thoroughly examined the site and is conversant with the requirements of the local jurisdiction.	1.00	DU	_____	_____
8	55 WORK TIMES Contractors and their Subcontractors shall schedule working hours between 8:00am and 6:00pm Monday through Friday. Requests to work on weekends and before or after these hours must be approved by the homeowner.	1.00	GR	_____	_____
9	75 STANDARD SPEC/GENERAL CONDITIONS The contractor by submission of a proposal, agrees to comply with all applicable conditions listed in the Standard Specification. Contractor also agrees that any building modification/repairs/ replacements that result in damage to the walls, ceiling, flooring, etc. shall be repaired to match the existing finish in the area. All fixtures and appliances to Energy Star certified.	1.00	GR	_____	_____
10	90 1 YEAR GENERAL WARRANTY Contractor shall remedy any defect due to faulty material or workmanship and pay for all damage to other work resulting therefrom, which appear within one year from final payment. Further, contractor shall furnish owner with all manufacturers' and suppliers' written warranties covering items furnished under this contract prior to release of the final payment.	1.00	DU	_____	_____
11	120 FINAL CLEAN Remove from site all construction materials, tools and debris. Sweep clean all exterior work areas. Vacuum all interior work areas, removing all visible dust, stains, labels and tags. Clean all windows referenced in specifications.	1.00	RM	_____	_____
12	9008 ENVIRONMENTAL REHAB--RRP REQUIREMENTS Any contractor performing renovation, repair, and painting projects that disturb lead-based paint in pre-1978 homes must comply with EPA 40 CFR Part 745(Lead; Renovation, Repair, and Painting Program), be certified by the EPA as a Renovation Firm and must use Certified Renovators who are trained by EPA-approved training providers to follow lead-safe work practices.	1.00	GR	_____	_____
Trade: 23	Electric				
13	7811 SMOKE DETECTORS Install a UL approved, ceiling mounted smoke/carbon and heat detector permanently wired into a receptacle box with battery back-up and interconnected with all other smoke detectors in the unit. To bring up to code.	5.00	EA	_____	_____

Location: 1 - General Requirements

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 23	Electric				

Trade: 24 Extermination

14	8305 EXTERMINATE TERMITES	1.00	DU	_____	_____
	House to be fumigated for the infestation of termites. House to be treated by a State of Florida properly insured, licensed pest control company. Property to be treated prior to the start of construction and any termite infestation to immediately reported. Copy of report and 5 year warranty to be submitted upon completion.				

Location Total: _____**Location: 2 - Exterior**

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 7	Masonry				

15	1170 BLOCK WALL REPAIR	1.00	SF	_____	_____
	Remove damaged block and patch wall by toothing replacement block of same dimensions into wall. Exterior texture to match existing.				

Trade: 10 Carpentry

16	3150 DOOR--EXTERIOR PANELED	2.00	EA	_____	_____
	All exterior doors to be 6 panel fiberglass specified to be replaced shall have composite jams and be complete with new hardware and new lever lockset using Kwikset or equal. All doors shall be installed in a new, approved frame complete with stops, weather-stripping, composite jambs, etc. After trimming and fitting of the door, all edges shall receive the same finish as the sides of the door. A door bumper and threshold are included on all exterior doors.				

All exterior doors shall have a one (1") inch throw dead bolt, single cylinder, thumb-screw/key operated inside. Dead bolt and lockset shall be keyed alike. Exterior doors shall be wind-loaded and installed to meet code. Deadbolt striker plates to be installed with 2" steel screws.

All thresholds shall be caulked to ensure protection from water intrusion per the manufacturer's installation instructions.

All doors to be prime painted, including the top and bottom, with two (2) coats of semi-gloss paint.

Peep hole to be added appropriate to homeowner's requirement.

No peep holes.

Location: 2 - Exterior

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
Trade: 15	Roofing				
17	<p>4502 FLAT ROOF REPLACEMENT</p> <p>Remove the existing roofing materials at dead level flat roof areas. Replace any deteriorated wood framing and sheathing. Re-sheath and install new built-up roof. The secondary water barrier is peel and stick. Flashing installed as required to pitched roof areas. Re-nail the roof deck to code. Two sheets or 64 sq.ft. of 1/2" cdx wood or matching thickness or material to be included in the bid.</p> <p>Furnish and install Liberty or equal 90# roll roofing peel and stick, in lieu of torch down roll roofing. Secondary water barrier to be peel and stick.</p> <p>Must notify the HQS at the time of roof installation so pictures of bare wood and water barrier installation, can be taken to verify compliance of specifications. Failure to notify could result in the roofing being rejected.</p> <p>Remove all areas of rotted, decayed fascia and soffit. Replace all rotted wood removed with new pressure treated wood. Caulk over joints.</p>	1.00	SQ	_____	_____
18	<p>4580 ROOF REPLACEMENT</p> <p>Remove and dispose of all roofing & defective sheathing. If applicable, remove the chimney to at least 6" below the roof line. Install a permanent cap on remaining portion of chimney. Resheath hole where chimney is removed. Cut a 1" wide vent at ridge board. Secondary water barrier Peel and Stick) provided as required by section 201.2. All associated mitigation is in compliance with the Hurricane Mitigation Retrofit Manual (Based on 553.844 F.S). Install preformed white aluminum, drip edge, and vent pipe boots. All shingles will be a 30 year architectural, fiberglass / asphalt UL Class A Fire Rated, pass UL 1997 110 mph wind load with a minimum 30 year warranty with a 15 year algae/ mildew resistant warranty. Drip edge will have a minimum width of two-inches and be constructed of either galvanized or aluminum. Replace all flashing. Install shingle-over ridge vent. Roof deck attachment and fasteners strengthened and corrected as required by Section 201.01. Color of shingles to be gray or black. Homeowner to pick color. Two sheets or 64 sq.ft. of 1/2" CDX wood or matching thickness or material to be included in the bid.</p> <p>Must notify the HQS at the time of roof installation so pictures of bare wood and water barrier installation, can be taken to verify compliance of specifications. Failure to notify could result in the roofing being rejected.</p> <p>Remove all areas of rotted, decayed fascia and soffit. Replace all rotted wood removed with new pressure treated wood sufficient for nailing new aluminum or vinyl fascia and vented soffit.</p> <p>Enclose all soffit with vented aluminum/vinyl and enclose all fascia boards with new vinyl or aluminum baked finish. Soffit and fascia to be white or bronze.</p>	1.00	SQ	_____	_____

Address: 10923 N 21st Street

Unit: Unit 01

Location: 2 - Exterior

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 15 Roofing

Remove all tree limbs less than 8' above roof line.

Location Total: _____

Location: 3 - Utility Room

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 22 Plumbing

19	7085	WATER HEATER--40 GAL. ELECTRIC	1.00	EA	_____	_____
<p>Dispose of water heater in legal dump. Install a 40 gallon, low profile, high recovery, glass lined, insulated to R-7, double element, electric water heater with 10 year warranty. Include pressure and temperature relief valve, discharge tube to within 6" of floor or to outside of structure, shut-off valve and electric supply. Install to Florida Building Code.</p>						

Location Total: _____

Location: 5 - Kitchen

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 22 Plumbing

20	6840	TRAP--REPLACE	1.00	EA	_____	_____
<p>Replace fixture trap and all corroded waste lines from wall stub out to fixture with PVC or polypropylene to include new vent stack. To include waste lines and vent stack coming from bathroom.</p>						

Location Total: _____

Unit Total for 10923 N 21st Street, Unit Unit 01: _____

Address Grand Total for 10923 N 21st Street: _____

Bidder: _____