



Location: 1 - General Requirements

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
<b>Trade: 1</b>	<b>General Requirements</b>				
	Contractor shall apply for and get all permits necessary for all Scope of Work Write Up (SWWU).				
7	<b>45 CONTRACTOR PRE-BID SITE VISIT</b> The contractor must inspect the property. Submission of a bid is presumptive evidence that the bidder has thoroughly examined the site and is conversant with the requirements of the local jurisdiction.	1.00	DU	_____	_____
8	<b>55 WORK TIMES</b> Contractors and their Subcontractors shall schedule working hours between 8:00am and 6:00pm Monday through Friday. Requests to work on weekends and before or after these hours must be approved by the homeowner.	1.00	GR	_____	_____
9	<b>75 STANDARD SPEC/GENERAL CONDITIONS</b> The contractor by submission of a proposal, agrees to comply with all applicable conditions listed in the Standard Specification.  Contractor also agrees that any building modification/repairs/ replacements that result in damage to the walls, ceiling, flooring, etc. shall be repaired to match the existing finish in the area.  All fixtures and appliances to Energy Star certified.	1.00	GR	_____	_____
10	<b>90 1 YEAR GENERAL WARRANTY</b> Contractor shall remedy any defect due to faulty material or workmanship and pay for all damage to other work resulting therefrom, which appear within one year from final payment. Further, contractor shall furnish owner with all manufacturers' and suppliers' written warranties covering items furnished under this contract prior to release of the final payment. All original warranties to be turned in to homeowner in a bound package. Copy of all warranties to be turned in to the City of Tampa at the completion of the job. include 5 year warranty for roof	1.00	DU	_____	_____
11	<b>120 FINAL CLEAN</b> Remove from site all construction materials, tools and debris. Sweep clean all exterior work areas. Vacuum all interior work areas, removing all visible dust, stains, labels and tags. Clean all windows referenced in specifications.	1.00	RM	_____	_____
12	<b>9008 ENVIRONMENTAL REHAB--RRP REQUIREMENTS</b> Any contractor performing renovation, repair, and painting projects that disturb lead-based paint in pre-1978 homes must comply with EPA 40 CFR Part 745(Lead; Renovation, Repair, and Painting Program), be certified by the EPA as a Renovation Firm and must use Certified Renovators who are trained by EPA-approved training providers to follow lead-safe work practices.	1.00	GR	_____	_____
<b>Trade: 23</b>	<b>Electric</b>				
13	<b>7811 SMOKE DETECTORS</b>	3.00	EA	_____	_____

Location: 1 - General Requirements

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 23 Electric

Install a UL approved, ceiling mounted smoke/carbon and heat detector permanently wired into a receptacle box with battery back-up and interconnected with all other smoke detectors in the unit. To bring up to code.

Trade: 24 Extermination

14	8305	<b>EXTERMINATE TERMITES</b>	1.00	DU	_____	_____
House to be fumigated for the infestation of termites. House to be treated by a State of Florida properly insured, licensed pest control company. Property to be treated prior to the start of construction and any termite infestation to immediately reported. Copy of report and 5 year warranty to be submitted upon completion.						

Location Total: \_\_\_\_\_

Location: 2 - Exterior

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 15 Roofing

15	4580	<b>ROOF REPLACEMENT</b>	1.00	SQ	_____	_____
Remove and dispose of all roofing & defective sheathing. If applicable, remove the chimney to at least 6" below the roof line. Install a permanent cap on remaining portion of chimney. Resheath hole where chimney is removed. Cut a 1" wide vent at ridge board. Secondary water barrier Peel and Stick) provided as required by section 201.2. All associated mitigation is in compliance with the Hurricane Mitigation Retrofit Manual (Based on 553.844 F.S). Install preformed white aluminum, drip edge, and vent pipe boots. All shingles will be a 30 year architectural, fiberglass / asphalt UL Class A Fire Rated, pass UL 1997 110 mph wind load with a minimum 30 year warranty with a 15 year algae/ mildew resistant warranty. Drip edge will have a minimum width of two-inches and be constructed of either galvanized or aluminum. Replace all flashing. Install shingle-over ridge vent. Roof deck attachment and fasteners strengthened and corrected as required by Section 201.01. Color of shingles to be gray or black. Homeowner to pick color. Two sheets or 64 sq.ft. of 1/2" CDX wood or matching thickness or material to be included in the bid.						

Must notify the HQS at the time of roof installation so pictures of bare wood and water barrier installation, can be taken to verify compliance of specifications. Failure to notify could result in the roofing being rejected.

Remove all areas of rotted, decayed fascia and soffit. Replace all rotted wood removed with new pressure treated wood. Caulk over joints.

Location: 2 - Exterior

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 15 Roofing

Remove all areas of rotten and decayed gable end. Provide and install all new hardi board and effected areas. Caulk and seal all joints, include all new trim work.

Trade: 21 HVAC

16	6180	<b>HVAC REPLACEMENT</b>	1.00	EA	_____	_____
----	------	-------------------------	------	----	-------	-------

Replace existing air conditioner with a new central heating and air conditioning system complete with all new controls and digital thermostat, control wiring, electrical , copper and necessary connections to create complete install to code. Minimum SEER required-15.0, concrete (or equal) pad. AH unit to be reinstalled in the original location with access to code. Perform proper test and balance at completion. Contractor is responsible for proper sizing of all new equipment and ductwork with the exception of the 7.5 KW heat strip. Provide owner w/factory warranty, manual, & 1 year contractor warranty. Installed to code.

Trade: 22 Plumbing

17	6739	<b>SEWER SERVICE</b>	1.00	LF	_____	_____
----	------	----------------------	------	----	-------	-------

Install a 4" schedule 40 PVCpipe from structure and connect to the public sanitary sewer system. Connect all new drain lines and insure smooth and proper operation, to include vent stacks. Install clean-outs as required by local codes. Regrade yard in work area, sow grass seed and spread straw to reestablish lawn. Replace all flooring in areas affected by new installation of sewer and drain lines. Flooring to match existing.

Location Total: \_\_\_\_\_

Location: 3 - Bathroom

Approx. Wall SF: 0

Ceiling/Floor SF: 0

Spec #	Spec	Quantity	Units	Unit Price	Total Price
--------	------	----------	-------	------------	-------------

Trade: 22 Plumbing

18	6960	<b>GRAB BARS AND FAUCET</b>	1.00	EA	_____	_____
----	------	-----------------------------	------	----	-------	-------

Remove old shower faucets. Provide and install 3 grab bars include Moen Model 82402 or equal tub/shower faucet & a shower head with a maximum 2.0 GPM flow rate.

Location Total: \_\_\_\_\_

Unit Total for 4507 Ashmore Drive, Unit Unit 01: \_\_\_\_\_

Address Grand Total for 4507 Ashmore Drive: \_\_\_\_\_

Bidder: \_\_\_\_\_